




REPUBLIC OF SERBIA
MINISTRY OF EUROPEAN INTEGRATION
MINISTRY OF FINANCE
Department for Contracting and Financing of
EU Funded Programmes

This project is financed by
the European Union



#EY
ЗА ТЕБЕ

ppf.rs | europa.rs | mei.gov.rs | cfcu.gov.rs



Updated Environmental Impact Assessment study for the project of rehabilitation, adaptation and reconstruction of navigation lock of HPP "Djerdap 2"

Project holder: Ministry of Construction, Transport and Infrastructure
Sector for water transport and safety of navigation



EU PPF - PROJECT PREPARATION FACILITY

DOCUMENT CONTROL SHEET

Contracting Authority: Delegation of the European Union to the Republic of Serbia
Ministry of Finance - Department for Contracting and Financing of EU Funded Programmes (CFCU)

Project Title: EU PPF - Project Preparation Facility

Beneficiary Country: Republic of Serbia

Service Contract Number: 48-00-00204/2014-28

Identification Number: EuropeAid/137119/IH/SER/RS

This project is implemented by the consortium of Louis Berger, GIZ, Stantec, Louis Berger doo and Epcco.



Project Holder:

Republic of Serbia, Ministry of Construction, Transport and Infrastructure

Authors:

1. Nebojša Pokimica, MSc Chemist/specialist in toxicological chemistry
2. Tanja Radovic, Chemical engineer/Ph.D.
3. Slobodan Zlatković, MSc Biologist
4. Marijana Jovanović, MSc Geology engineer
5. Nataša Djokic, MSc Geology engineer
6. Pavle Cvetić, MSc Landscape architect
7. Bojana Lalovic, MSC Environmental Protection Engineer



EU PPF - PROJECT PREPARATION FACILITY

List of abbreviations and acronyms

NL	Navigation lock
DG NEAR	(EU) Directorate General for European Neighbourhood Policy and Enlargement Negotiations
EU/EUDEL	European Union Delegation (to the Republic of Serbia)
DTD	Danube-Tisa-Danube
EAR	European Agency for Reconstruction
EU	European Union
IPA	(EU) Instrument for Pre-Accession Assistance
IPF	(EU) Infrastructure Project Facility
JASPERS	(EU) Joint Assistance to Support Projects in European Region
CM	Cadastar municipality
MEI	Ministry for European Integration
MoCTI	Ministry of Construction, Transport and Infrastructure
MEP	Ministry of Environmental Protection
IFIs	International Financial Institutions
MoF - CFCU	Ministry of Finance - Department for Contracting and Financing of EU Funded Programmes
NAD	'Needs of the Republic of Serbia for International Assistance 2014-17 with projections until 2020'
NIPAC	National IPA Coordinator
NIC	National Investment Committee
PT	Project Task
PLC	Programmable logic controller
WWTP	Waste Water Treatment Plant
PPF6	Project Preparation Facility 6 – Project Preparation of Investment Projects
PPF7	Project Preparation Facility 7
PPF8	Project Preparation Facility 8
EIA	Environmental Impact Assessment
SIP	Stakeholder Involvement Plan
SIDA	Swedish International Development Cooperation Agency
PSC	Project Steering Committie
HPP	Hidropower plant
HPNS	Hydropower and navigation system
SCADA	Supervisory control and data acquisition

EU PPF - PROJECT PREPARATION FACILITY

Content

GENERAL INFORMATION	5
1 INTRODUCTION	17
1.1 Background for the Study	17
1.1.1 Legislation	18
1.1.2 Technical Documentation	19
2 INFORMATION ON PROJECT HOLDER	22
3 DESCRIPTION OF LOCATION	23
4 PROJECT DESCRIPTION	27
4.1 Facilities description	27
4.2 Description of planned works	29
4.2.1 Architectural works	29
4.2.2 Rehabilitation of constructions	30
4.2.3 Roads	31
4.2.4 Hydraulic part	31
4.2.1 Electrical power installations	33
4.2.2 Mechanical installations	35
5 OVERVIEW OF MAIN ALTERNATIVES CONSIDERED BY THE PROJECT HOLDER	41
6 DESCRIPTION OF THE ENVIRONMENT CONDITIONS	42
7 DESCRIPTION OF POSSIBLE SIGNIFICANT EFFECTS OF THE PROJECT ON THE ENVIRONMENT	45
8 ENVIRONMENTAL IMPACT ASSESSMENT IN CASES OF ACCIDENTS	47
9 TRANSBOUNDARY ENVIRONMENTAL IMPACT	51
10 DESCRIPTION OF MEASURES PROVIDED TO PREVENT, REDUCE AND ELIMINATE SIGNIFICANT ADVERSE IMPACTS	52
11 ENVIRONMENTAL IMPACT MONITORING PROGRAM	65
11.1 Overview of the state of the environment before the start of the operation of the project at locations where the impact on the environment is expected	65
11.2 Parameters on the basis of which harmful effects on the environment can be determined	65
12 DATA ON TECHNICAL DEFICIENCIES	72

Annexes:

Annex 1 – Layout of navigation lock of HPNS "Djerdap 2"

Annex 2 – Layout plans



EU PPF - PROJECT PREPARATION FACILITY

GENERAL INFORMATION



EU PPF - PROJECT PREPARATION FACILITY

		ИЗВОД О РЕГИСТРАЦИЈИ ПРИВРЕДНОГ СУБЈЕКТА		Република Србија Агенција за привредне регистре
8000064546041				

ОСНОВНИ ИДЕНТИФИКАЦИОНИ ПОДАТАК

Матични / Регистарски број	20407441
----------------------------	----------

СТАТУС

Статус привредног субјекта	Активан
----------------------------	---------

ПРАВНА ФОРМА

Правна форма	Друштво са ограниченом одговорношћу
--------------	-------------------------------------

ПОСЛОВНО ИМЕ

Пословно име	DRUŠTVO ZA ZAŠTITU ŽIVOTNE SREDINE I ODRŽIVI RAZVOJ DVOPER DOO BEOGRAD (STARI GRAD)
Скраћено пословно име	DVOPER DOO BEOGRAD

ПОДАЦИ О АДРЕСАМА

Адреса седишта	
Општина	Београд-Стари Град
Место	Београд-Стари Град
Улица	Нушићева
Број и слово	10
Спрат, број стана и слово	4 / 20 /

ПОСЛОВНИ ПОДАЦИ

Подаци оснивања	
Датум оснивања	11. април 2008
Време трајања	
Време трајања привредног субјекта	Неограничено
Претежна делатност	
Шифра делатности	7120
Назив делатности	Техничко испитивање и анализе
Остали идентификациони подаци	
Порески Идентификациони Број (ПИБ)	105557340
Подаци од значаја за правни промет	

Дана 09.07.2020. године у 13:16:03 часова

Страна 1 од 3



EU PPF - PROJECT PREPARATION FACILITY

Текући рачуни	
	170-0030005721012-08
	170-0030005721006-26
	170-0030005721001-41
	340-0000010043135-83
	170-0030005721011-11
	170-0030005721002-38
	340-0000011024778-74
170-0030005721004-32	
Подаци о статусу / оснивачком акту	
Не постоји обавеза овере измена оснивачког акта	Датум важећег статута <input type="text"/>
	Датум важећег оснивачког акта <input type="text"/>

Законски (статутарни) заступници			
Физичка лица			
1. Име	<input type="text" value="Небојша"/>	Презиме	<input type="text" value="Покимица"/>
ЈМБГ	<input type="text" value="0101972780015"/>		
Функција	<input type="text" value="Директор"/>		
Ограничење супотписом	<input type="text" value="не постоји ограничење супотписом"/>		

Директори / чланови одбора директора			
Директори			
Чланови одбора директора			
1. Име	<input type="text" value="Небојша"/>	Презиме	<input type="text" value="Покимица"/>
ЈМБГ	<input type="text" value="0101972780015"/>		

Прокуристи			
Појединачна прокура			
1. Име	<input type="text" value="Ратко"/>	Презиме	<input type="text" value="Ђорђевић"/>
ЈМБГ	<input type="text" value="0405943330077"/>		

Чланови / Сувласници	
Подаци о члану	
Пословно име	<input type="text" value="DVOKUT-ECRO DOO"/>
Регистарски / Матични број	<input type="text" value="00539651"/>

Дана 09.07.2020. године у 13:16:03 часова

Страна 2 од 3



EU PPF - PROJECT PREPARATION FACILITY

Држава	Хрватска	
Подаци о капиталу		
Новчани		
износ	датум	
Уписан: 3.000,00 EUR, у противвредности од 247.026,90 RSD		
износ	датум	
Уписан: 3.752.973,10 RSD		
износ	датум	
Уплаћен: 3.000,00 EUR, у противвредности од 247.026,90 RSD	28. март 2008	
износ	датум	
Уплаћен: 3.752.973,10 RSD	4. март 2015	
Удео	износ(%)	
	100,000000000000	

Основни капитал друштва		
Новчани		
износ	датум	
Уписан: 3.000,00 EUR, у противвредности од 247.026,90 RSD		
износ	датум	
Уписан: 3.752.973,10 RSD		
износ	датум	
Уплаћен: 3.000,00 EUR, у противвредности од 247.026,90 RSD	28. март 2008	
износ	датум	
Уплаћен: 3.752.973,10 RSD	4. март 2015	



Регистратор: Владан Маглов

Дана 09.07.2020. године у 13:16:03 часова

Страна 3 од 3



EU PPF - PROJECT PREPARATION FACILITY



ИНЖЕЊЕРСКА КОМОРА СРБИЈЕ

ЛИЦЕНЦА

ОДГОВОРНОГ ПРОЈЕКТАНТА

На основу Закона о планирању и изградњи и
Статута Инжењерске коморе Србије


УПРАВНИ ОДБОР ИНЖЕЊЕРСКЕ КОМОРЕ СРБИЈЕ
утврђује да је

Тања Т. Радовић
дипломирани инжењер технологије
ЛИБ 11580077263
одговорни пројектант
технолошких процеса

Број лиценце
371 M423 13



У Београду,
4. јула 2013. године

ПРЕДСЕДНИК КОМОРЕ

Милован Главоњић
дипл. инж. ел.



EU PPF - PROJECT PREPARATION FACILITY

Број: 12-02/342662
Београд, 25.03.2019. године



На основу члана 75. Статута Инжењерске коморе Србије
("СГ РС", бр. 88/05, 16/09 и 27/16), а на лични захтев члана Коморе,
Инжењерска комора Србије издаје

ПОТВРДУ

Којом се потврђује да је Тања Т. Радовић, дипл. инж. техн.
лиценца број

371 M423 13

за

одговорног пројектанта технолошких процеса

на дан издавања ове потврде члан Инжењерске коморе Србије, да је
измирио обавезу плаћања чланарине Комори закључно са 04.07.2019.
године, као и да му одлуком Суда части издата лиценца није одузета.



Потпредседник Управног одбора
Инжењерске коморе Србије

Латинка Обрадовић
Латинка Обрадовић, дипл. грађ. инж.



EU PPF - PROJECT PREPARATION FACILITY





EU PPF - PROJECT PREPARATION FACILITY

Број: 02-12/405935
Београд, 24.02.2021. године



На основу члана 14. Статута Инжењерске коморе Србије
("СГ РС", бр. 36/19) а на лични захтев члана Коморе,
Инжењерска комора Србије издаје

ПОТВРДУ

Којом се потврђује да је Маријана С. Јовановић, дипл. инж. геол.
лиценца број

392 M517 13

за

одговорног пројектанта хидрогеолошких подлога и објеката

на дан издавања ове потврде члан Инжењерске коморе Србије, да је измирио
обавезу плаћања чланарине Комори за текућу годину, односно до 08.08.2021.
године, као и да му није изречена мера пред Судом части Инжењерске
коморе Србије



Председница Инжењерске коморе Србије

Марица М.
Марица Мијајловић, дипл. инж. арх.



EU PPF - PROJECT PREPARATION FACILITY





EU PPF - PROJECT PREPARATION FACILITY

Број: 02-12/405934
Београд, 24.02.2021. године

На основу члана 14. Статута Инжењерске коморе Србије ("СГ РС", бр. 36/19) а на лични захтев члана Коморе, Инжењерска комора Србије издаје

ПОТВРДУ

Којом се потврђује да је Маријана С. Јовановић, дипл. инж. геол.
лиценца број
492 Н778 13
за
одговорног извођача радова на изради хидрогеолошких подлога

на дан издавања ове потврде члан Инжењерске коморе Србије, да је измирио обавезу плаћања чланарине Комори за текућу годину, односно до 08.08.2021. године, као и да му није изречена мера пред Судом части Инжењерске коморе Србије

Председница Инжењерске коморе Србије
Марица М.
Марица Мијајловић, дипл. инж. арх.





EU PPF - PROJECT PREPARATION FACILITY





EU PPF - PROJECT PREPARATION FACILITY

Број: 02-12/406006
Београд, 25.02.2021. године



На основу члана 14. Статута Инжењерске коморе Србије
("СГ РС", бр. 36/19) а на лични захтев члана Коморе,
Инжењерска комора Србије издаје

ПОТВРДУ

Којом се потврђује да је Наташа Ђ. Ђокић, дипл. инж. геол.
лиценца број

A201 00916 19

за

**одговорног пројектанта за стручну област геолошко инжењерство,
ужа стручна област хидрогеологија (ознака ГТП 10-02)**

на дан издавања ове потврде члан Инжењерске коморе Србије, да је измирио
обавезу плаћања чланарине Комори за текућу годину, односно до 09.03.2021.
године, као и да му није изречена мера пред Судом части Инжењерске
коморе Србије



Председница Инжењерске коморе Србије

Марица М.
Марица Мијајловић, дипл. инж. арх.

EU PPF - PROJECT PREPARATION FACILITY

1 INTRODUCTION

Over the past three decades, transport infrastructure and inland waterway transport in Serbia have suffered negative impacts due to lack and inadequate maintenance resulting from various internal and external factors. Serbia has not had the opportunity to improve the infrastructure of inland waterways, using modern and advanced solutions to respond to these challenges, which has led to problems in water transport. For that reason, the revitalization of infrastructure networks is one of the main priorities of Serbia.

In 2007 and 2008, the European Agency for Reconstruction (EAR) financed the Development of project and tender documentation for the revitalization of Serbian navigation locks "Djerdap 1" and "Djerdap 2" (Ref. EuropeAid/123966/D/SER/IU), which was implemented a consortium of companies Witteveen + Bos and Nebest from the Netherlands and Energoprojekt-Hidroinzenjering from Serbia. Within the project documentation prepared in accordance with the standards of the European Union, a procedure for assessing the impact of the project on the environment has been initiated. In that context, and in accordance with the provisions of the Law on Environmental Impact Assessment ("Official Gazette of RS", No. 135/2004) and other relevant legislation, a Study on Environmental Impact Assessment of the navigation lock revitalization was prepared. The Study was approved on October 8, 2009 by the Ministry of Environment and Spatial Planning of the Republic of Serbia, number 353-02-00692/2009-02.

Upon completion of the project and technical documentation (including the Environmental Impact Assessment Study), the works on the adaptation of the ship navigation lock of HPP "Djerdap 2" were mostly not performed, except for regular and overhaul maintenance.

Taking into account the current condition of the facilities and equipment of the navigation lock, the development of the Preliminary design, Preliminary design and Feasibility study for the rehabilitation, adaptation and reconstruction of the navigation lock system "Djerdap 2" was started. With the development of the conceptual design, there was a need to update the existing Study on Environmental Impact Assessment of the project of revitalization of the navigation lock "Djerdap 2".

Based on the request of the Ministry of Construction, Transport and Infrastructure (project holder), the Ministry of Environmental Protection of the Republic of Serbia determined the scope and content of the updated study (Decision No. 353-02-150 / 2021-03 of March 8, 2021) and the updating of the Study was proceeded .

1.1 Background for the Study

The following substrates were used in the study of the impact assessment:

- Relevant legislation of the Republic of Serbia, the European Union and the International Convention
- Technical documentation.

EU PPF - PROJECT PREPARATION FACILITY

1.1.1 Legislation

EU Legislation

1. Directive on the assessment of the effects of certain public and private projects on the environment 2011/92 / EU, as amended by Directive 2014/52 / EU
2. Directive 2001/42 / EC of the European Parliament and of the Council on the assessment of the effects of certain plans and programs on the environment
3. Water Framework Directive 2000/60 / EC, as amended by Decision no. 2455/2001 / EC, Directive 2008/32 / EC, Directive 2008/105 / EC, Directive 2009/31 / EC, Directive 2013/39 / EU, Directive 2013/64 / EU, Directive 2014/101 / EU
4. Directive 92/43 / EEC on the conservation of natural habitats and of wild fauna and flora, as amended by Directive 97/62 / EC, Regulation 1882/2003, Directive 2006/105 / EC and Directive 2013/17 / EU
5. Directive 2009/147 / EC on the conservation of wild birds, as amended by Directive 2013/17 / EU and Regulation (EU) 2019/1010)

International Conventions

1. Convention on Environmental Impact Assessment in a Transboundary Context (Law on Ratification of the Convention on Environmental Impact Assessment in a Transboundary Context, "Official Gazette of RS - International Agreements", No. 102/2007),
2. Kyoto Protocol to the United Nations Framework Convention on Climate Change (Law on Ratification of the Kyoto Protocol to the United Nations Framework Convention on Climate Change, "Official Gazette of RS", No. 88/2007 and 38/2009),
3. Convention on the Conservation of Migratory Species of Wild Animals (Law on Ratification of the Convention on the Conservation of Migratory Species of Wild Animals, "Official Gazette of RS - International Agreements", No. 102/2007),
4. Multilateral Agreement of the Countries of Southeast Europe on the Implementation of the Convention on Environmental Impact Assessment in a Transboundary Context (Law on Ratification of the Multilateral Agreement of the Countries of Southeast Europe on the Implementation of the Convention on Environmental Impact Assessment in a Transboundary Context, "Official Gazette of RS", no. 12/18),
5. Convention on Cooperation for the Protection and Sustainable Use of the Danube River (Law on Ratification of the Convention on Cooperation for the Protection and Sustainable Use of the Danube River ("Official Gazette of the FRY - International Agreements", No. 2 / 2003-26)).

Legislative of the Republic of Serbia

1. Law on Environmental Impact Assessment ("Official Gazette of RS", No. 135/04 and 36/09),
2. Law on Strategic Environmental Assessment ("Official Gazette of RS", No. 135/04, 88/10)



EU PPF - PROJECT PREPARATION FACILITY

3. Law on Planning and Construction ("Official Gazette of RS", No. 72/2009, 81/2009 - corrigendum, 64/2010 - US decision, 24/2011, 121/2012, 42/2013 - US decision, 50/2013 - decision US, 98/2013 - decision US, 132/2014, 145/2014, 83/2018, 31/2019 and, 37/2019 - other law and 9/2020);
4. Law on Environmental Protection ("Official Gazette of RS", No. 135/2004, 36/2009, 36/2009 - other law, 72/2009 - other law, 43/2011 - US decision, 14 / 2016, 76/2018 and 95/2018 - other law);
5. Law on Nature Protection ("Official Gazette of RS", No. 36/09, 88/10, 91/10 - amended, 14/16, 95/18 - other law);
6. Rulebook on proclamation and protection of strictly protected and protected wild species of plants, animals and fungi ("Official Gazette of RS", No. 5/10, 47/11, 32/16, 98/16);
7. Law on Protection against Non-Ionizing Radiation ("Official Gazette of RS", No. 36/09);
8. Law on Ionizing Radiation Protection and Nuclear Safety ("Official Gazette of RS", No. 36/09 and 93/12);
9. Law on Cultural Heritage ("Official Gazette of RS", No. 71/94, 52/11 - other law, 99/11 - other law, 6/20 - other law);
10. Law on Transport of Dangerous Goods ("Official Gazette of RS", No. 88/10, 104/16 - other law, 83/18 - other law);
11. Law on Chemicals ("Official Gazette of RS", No. 36/09, 88/10, 92/11, 93/12 and 25/215);
12. Law on Fire Protection ("Official Gazette of RS", No. 111/09);
13. Law on Disaster Risk Reduction and Emergency Management ("Official Gazette of RS", No. 87/2018);
14. Law on Air Protection ("Official Gazette of RS", No. 36/2009 and 10/2013);
15. Decree on conditions for monitoring and air quality requirements ("Official Gazette of RS", No. 11/2010, 75/2010 and 63/2013);
16. Law on Waters ("Official Gazette of RS", No. 30/2010, 93/2012, 101/2016, 95/2018 and 95/2018 - other law);
17. Law on Land Protection ("Official Gazette of RS", No. 112/15);
18. Law on Environmental Noise Protection ("Official Gazette of RS", No. 36/2009 and 88/2010);
19. Law on Waste Management ("Official Gazette of RS", No. 36/2009, 88/2010, 14/2016 and 95/2018 - other law);
20. Law on Packaging and Packaging Waste ("Official Gazette of RS", No. 36/09, 95/18-other law)
21. Law on Safety and Health at Work ("Official Gazette of RS", No. 101/05, 91/151 and 113/17 - other law) and relevant bylaws.

1.1.2 Technical Documentation

The Preliminary Design and the Feasibility Study for the Rehabilitation, Adaptation and Reconstruction of the navigation lock HPNS "Djerdap 2" were used to prepare the Impact Assessment Study.

CONTENT OF THE PRELIMINARY DESIGN AND FEASIBILITY STUDY OF SANITATION, ADAPTATION AND RECONSTRUCTION OF THE NAVIGATION LOCK HENS "DJERDAP 2":



EU PPF - PROJECT PREPARATION FACILITY

ARCHIVAL PROJECT

18072-IDP-00	0. MAIN NOTEBOOK , "Energoprojekt-Hidroinženjering" a.d. Belgrade, August 2020, Belgrade
	1. ARCHITECTURE PROJECT , "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020, Belgrade
18072-IDP-I-01	CONTROL TOWER GONDOLA
18072-IDP-I-02	TECHNOLOGICAL ROOMS
	2. CONSTRUCTION PROJECT , "Energoprojekt hidroinženjering" a.d., April 2020.
18072-IDP-II-01.1	CONTROL TOWER GONDOLA
18072-IDP-II-01.2	TECHNOLOGICAL ROOMS
18072-IDP-II-01.3	CONCRETE FACILITIES
18072-IDP-II-02.1	ROAD PROJECT
	3. HYDROTECHNICAL INSTALLATIONS PROJECT , "Energoprojekt hidroinženjering" a.d., April 2020.
18072-IDP-III-01	WORKS ON THE EMBANKMENT ON THE RIVER SIDE OF THE DOWNSTREAM BERTHING AREA
	4. ELECTRIC POWER INSTALLATIONS PROJECT , "Energoprojekt hidroinženjering" a.d., April 2020.
18072-IDP-IV-01	ELECTROHYDRAULIC DOOR AND CLOSURE DRIVE CONTROL SYSTEM
18072-IDP-IV-02	ELECTROHYDRAULIC DRIVE NETWORK CONTROL SYSTEM
18072-IDP-IV-03	POWER SUPPLY CONSUMER POWER SUPPLY SYSTEM ELECTRIC ENERGY
18072-IDP-IV-04	TRAFFIC SIGNALING SYSTEM
18072-IDP-IV-05	HEATING, VENTILATION AND AIR CONDITIONING SYSTEM
18072-IDP-IV-06	EXTERIOR AND INTERIOR LIGHTING SYSTEM
18072-IDP-IV-07	DISCHARGE AND DRAINAGE SYSTEM
18072-IDP-IV-08	GUIDE AND DOOR THRESHOLD HEATING SYSTEM
18072-IDP-IV-09	CRANES
18072-IDP-IV-10	STABLE FIRE EXTINGUISHING SYSTEM
18072-IDP-IV-11	CENTRAL LUBRICATION SYSTEM OF WORKING DOOR DOORS
18072-IDP-IV-12	ACCOMPANYING SYSTEMS
	water level measurement system
	system for measuring meteorological parameters,
	sound system,
	radar system,
	video surveillance system
	conversation recording system,
	radio communication system,



EU PPF - PROJECT PREPARATION FACILITY

	vessel detection system
	telephony system
	5. TELECOMMUNICATION AND SIGNAL INSTALLATIONS PROJECT, "Energoprojekt-Hidroinženjering" a.d. Belgrade and "GARDAL" d.o.o. Nis, Belgrade, April 2020
18072-IDP-V-01	AUTOMATIC FIRE ALARM SYSTEM
	6. MACHINE INSTALLATION PROJECT
18072-IDP-VI-01	ELECTROHYDRAULIC DOOR AND CLOSURE DRIVES, "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020
18072-IDP-VI-02	ELECTROHYDRAULIC PLANTS OF THE PROTECTIVE NETWORK, "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020
18072-IDP-VI-03	WORKING DOORS LIFTING HEAD, "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020
18072-IDP-VI-04	WORKING DOUBLE WING DOORS, LOWER HEAD, "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020
18072-IDP-VI-05	HYDROMECHANICAL EQUIPMENT OF THE PROTECTIVE NETWORK, "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020
18072-IDP-VI-06	ENTRANCE GRATING "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020
18072-IDP-VI-07	HEATING AND VENTILATION SYSTEM OF OPERATING ROOMS AND CONTROL TOWER, "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020
18072-IDP-VI-08	STABLE FIRE EXTINGUISHING SYSTEM, "Energoprojekt-Hidroinženjering" a.d. Belgrade and "Shipping" d.o.o. Belgrade, April 2020
18072-IDP-VI-09	CRANES, "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020
18072-IDP-VI-10	DISCHARGE AND DRAINAGE SYSTEM, "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020
18072-IDP-VI-11	CENTRAL LUBRICATION SYSTEM OF WORKING DOOR WINGS, "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020
18072-IDP-EZP-01	FIRE PROTECTION STUDY, "Energoprojekt-Hidroinženjering" a.d. Belgrade and "Cepting" d.o.o. Belgrade, April 2020
18072-IDP-EEE-01	ENERGY EFFICIENCY STUDY, "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020
18072-SO-01	FEASIBILITY STUDY, "Energoprojekt-Hidroinženjering" a.d. Belgrade, April 2020



EU PPF - PROJECT PREPARATION FACILITY

2 INFORMATION ON PROJECT HOLDER

Name	Republic of Serbia Ministry of construction, transport and infrastructure Sector for water transport and safety of navigation
Adress:	Nemanjina street 22-26 , Belgrade, Serbia
Telephone number:	+38111/3621-698 +38111/3619-491
E- mail:	veljko.kovacevic@mgsi.gov.rs

EU PPF - PROJECT PREPARATION FACILITY

3 DESCRIPTION OF LOCATION

Hydropower and navigation system "Djerdap 2" administratively belongs to the Bor district, ie the municipality of Negotin. The municipality of Negotin is surrounded by the municipalities of Kladovo, Majdanpek, Bor and Zajecar, and it also borders Bulgaria (border length 41 km) and Romania (border length 35.5 km).

HEPS "Djerdap 2" was built on the stationing km 862 + 800 on the profile "Kusjak", 2 km upstream from the beginning of the Veliko ostrvo (Ostrovul Mare), which divides the Danube into the main course and the left tributary Gogoš.

HPNS "Djerdap 2" is located 80 km downstream from HPNS "Djerdap 1", 70 km from Kladovo, 67 km from the Romanian town of Turn Severin and upstream 2 km from Prahovo and 17 km from the confluence of the Timok and the Danube River.

On the Gogos tributary, about 11.5 km upstream, is stationed the second barrier point of the hydropower and navigation system "Djerdap 2" - the Romanian Gogos dam.

HPP "Djerdap 2" occupies the following cadastral parcels: 15809/4, 15809/5, 15809/6, 5675/2, 5006, all in CM Dusanovac; 7642/1, CM Mihajlovac and 6048/1, CM Prahovo.



Pedological characteristics: The following lands predominate in the area of "Djerdap 2": vertisol, chernozem, fluvial soils and wetland.



EU PPF - PROJECT PREPARATION FACILITY

Geological structure of HPP "Djerdap 2": Myopliocene, mostly clay-marl rocks, which belong to the layers of tortones, sarmats, upper meots and lower pont, participate in the terrain structure of the regional area around "Djerdap 2". They lie over the Lower Cretaceous formations, which is developed in the carbonate-lapa facies, and are covered with thick Quaternary deposits and deposits of the Danube terraces.

Seismic characteristics: Based on seismic hazard maps, seismic parameters for the HPP "Djerdap 2", the maximum earthquake intensity for the return period of 475 years is VIII degrees of the Mercalli scale, and for 975 years VIII-IX degrees of the Mercalli scale.

Hydrological characteristics: The Danube (over 30 km long), Timok, Sikolska river, Jasenička river, Slatinska river and Zamna flow through the territory of the municipality of Negotin.

The flows of the Danube vary in a wide range from 1,500 m³/s to 16,000 m³/s, and can reach as much as 23,000 m³/s with a probability of occurring once in 10,000 years. The average multi-year flow of the Danube from 1926 to 1975 on the profile of HPP "Djerdap 2" was 5,656 m³/s, while the average value of a series of minimum flows was 2,253 m³/s. The large waters of the Danube are occure in April, partly in May, and the small waters twice a year in mid-September and late January. Absolute annual minimum usually occurs during the winter.

Based on the hydrological data processing of Danube river on the profile of HPP "Djerdap 2", the following characteristic hydrological quantities were obtained:

- high waters of the Danube for the return period of 10,000 years Q0.01% = 22,350 m³/s, high waters for the return period of 1,000 years Q0.1% = 19,300 m³/s, for the return period of 100 years Q1% = 16,200 m³/s,
- minimum waters of the Danube for the return period of 1,000 years Q0.1% = 950 m³/s, small waters for the return period of 100 years Q1% = 1,070 m³/s.

The width of the Danube at the site of the navigation lock "Djerdap 2", to the Romanian Veliko ostrvo (Ostrovl Mare), is 500 m.

Proximity to the sanitary protection zone, watercourses and water supply sources: HPP "Djerdap 2", as well as the settlement of Dušanovac, are supplied with drinking water from the spring "Barbaros", which is owned by HPP "Djerdap 2". The spring is formed by three wells and a catchment well. According to the data of the Republic Water Directorate, in the water area of Donji Dunav and the municipality of Negotin, there is a source of public water supply to the settlement "Konace". The area of sanitary protection zones around the spring is 35.74 ha (Zones I and II) and 26.76 ha (Zone III).

Climatic characteristics: The lower Danube basin is characterized by a continental climate. The average annual temperature in Negotin is 12.4 ° C, the warmest months are July and August, and the coldest are January and December. Data on the sum of monthly and annual precipitation show that on average most precipitation is excreted in December, June and May, ie 633.7 mm annually. The area of Negotin and Djerdap



EU PPF - PROJECT PREPARATION FACILITY

has frequent winds, with average speeds of over 1.5 m/s throughout the year, and the west-northwest wind has the highest frequency.

Flora, fauna and natural values: There are no protected plant and animal species at the location in question. With the construction of HPP "Djerdap 2" and the regulation of riverbeds, the ichthyofauna has undergone the most changes in composition and structure - the Black Sea migratory species (sturgeon species and herring) have disappeared from Djerdap accumulation, while the population of species such as sturgeon, carp, catfish, pike, perch, asp, barbel has increased. New fish species have also appeared, such as grass carp, bighead carp, silver carp, brown bullhead, pumpkinseed. According to the data from the Central Register of Protected Natural Resources, there are several protected areas on the territory of the municipality of Negotin, however, none of them is close to HPNS (the nearest is 11 km as the crow flies).

Landscape characteristics: Apart from the road number 168 and the uncategorized road which connects the settlement of Prahovo with the road 168, the bank of the Danube in the immediate vicinity of HPP "Djerdap 2" is undeveloped, covered with grass and low vegetation. About two kilometers upstream from Djerdap 2, there is Kusjak beach.

Immovable cultural property: According to the Decision on the determination of immovable cultural property of exceptional and great importance ("Official Gazette of the SRS" No. 47/87), there are no protected immovable cultural property in this area.

Settlements and population: The facilities of the navigation lock HPP "Djerdap 2" are mostly located in the settlement of Dusanovac, while a smaller part belongs to Prahovo and Mihajlovac. The number of inhabitants in the entire municipality has been in constant decline since 1961, and the municipality is also characterized by external migrations of inhabitants (25.84% of the inhabitants of the municipality).

Existing commercial and residential facilities and infrastructure facilities: The following commercial facilities are located in the settlement of Prahovo: IHP Prahovo (Elixir group), Luka Prahovo and NIS bunker station. The backbone of the industrial structure of the economy of the entire municipality of Negotin is the factory IHP Elixir group Prahovo, which produces phosphoric acid and highly concentrated phosphorus fertilizers.



EU PPF - PROJECT PREPARATION FACILITY




Figure 3-1- Danube bank in the vicinity of HPP Djerdap 2

EU PPF - PROJECT PREPARATION FACILITY

4 PROJECT DESCRIPTION

4.1 Facilities description

HPNS "Djerdap 2" is the second joint Serbian-Romanian hydroelectric power plant located on the Danube. It consists of a basic power plant, two additional power plants, two overflow dams, two navigation locks and two distribution plants. Each side, Serbian and Romanian, has one of the mentioned facilities.

During the first installation, the entire installed equipment of the ship's lock was made in Romania, whose concept is outdated, but due to regular maintenance on the ship's lock HPP "Djerdap 2", there have been no major emergency situations so far.

Due to the obsolescence of the equipment as well as due to the necessary strengthening of the equipment on the deceleration front, due to the increase in the level of the upstream lake, it is necessary to adapt the equipment, devices and systems according to the following criteria:

- Expiration of working life, which increases the cost of exploitation, i.e. maintenance of constructed systems;
- High exploitation risk that in addition to failures, due to the instability of the parameters, delays may occur due to mechanical breakage of the drive equipment;
- Impossibility to procure spare parts on the market, due to the cessation of production of equipment parts older than 20 years
- as well as repairing damage to the reinforced concrete parts of the ship's lock.

The adaptation of the navigation lock of HPP "Djerdap 2" will enable the smooth flow of river traffic on the Danube.

The Serbian lock is located along the right bank of the main course of the Danube. It has one chamber with access from the upstream accumulation lake when the translation is done in the downstream direction, and with access from the lower water zone when the translation is done in the upstream direction. In terms of construction, it consists of several functionally dependent facilities and units:

- Upstream berthing area (width 100 - 180 m and length 510 m),
- Upstream (upper) head,
- Lock chamber (width 34 m and useful length 310 m)
- Control tower,
- Downstream (lower) head,
- Downstream berthing area (width 100 - 180 m and length (river line) 510 m, i.e. 100 -180 m (coastline)).
- Layout of navigation lock layout is given in figure 4-1 and in Annex 1.



EU PPF - PROJECT PREPARATION FACILITY




Figure 4-1. Layout of navigation lock at HPP Djerdap 2

EU PPF - PROJECT PREPARATION FACILITY

4.2 Description of planned works

4.2.1 Architectural works

Architectural works include the rehabilitation of the control tower gondola and the reconstruction and modernization of technological premises.

Control tower gondola remediation

Remediation of the navigation lock control tower gondola at the HPP "Djerdap 2" includes craft works inside the gondola, adaptation of all rooms and craft works related to the replacement of installed (existing) materials that line the gondola. The project envisages all the necessary and required works, as well as the use of modern materials.

The conceptual design envisages the following:

- Removal of dilapidated waterproofing and installation of new thermal and hydro insulation using modern materials, in accordance with the recommendations of the Study on Energy Efficiency,
- Dismantling of the existing fence on the roof of the gondola of the command tower and installation of a new metal fence with anti-corrosion coating and final painting, as well as installation of metal climbers with a back guard,
- Removal of the glass facade of the gondola and installation of a semi-structural facade.
- Removal of load-bearing floorboards supported by a space grid, inspection of existing roof prefabricated concrete slabs and installation of new floor slabs; and roof slabs if needed.
- Dismantling of the existing metal sheets of the upper and lower lining of the gondola and installation of flat aluminum panels 5 cm thick on the appropriate substructure. Thermal insulation of the lower slab of the gondola will be performed at the lower side of the prefabricated concrete slabs.
- Dismantling of existing suspended ceilings and installation of new, non-combustible ceilings made of modern materials, over a fireproof substructure. Thermal insulation will be placed above the suspended ceiling.
- Removal of existing floor coverings inside the gondola and installation of new ones (antistatic floor in the control room and server room, PVC floor in the entrance hall and room for heating and ventilation systems, PVC flooring, ceramic tiles in the toilet).
- Removal of paint and smoothing compound from all interior walls and ceilings in the bathroom and re-smoothing and painting.
- Removal and replacement of floor and wall ceramic tiles, dismantling and replacement of internal plumbing and sanitary elements.
- Replacement of wooden doors and glass aluminum partitions with aluminum doors and fixed glazed partitions with glass doors.

EU PPF - PROJECT PREPARATION FACILITY

Reconstruction and modernization of technological premises

Within the navigation lock at HPP "Djerdap 2", there are technological premises for storing electrical machinery that initiates the opening and closing of doors at the navigation lock.

The scope of architectural (craft) works envisages the replacement of existing materials which have been used to finish the interior of the technological premises (walls, ceilings and floors). Craft works are planned to repair the existing damage, which endangers the employees and the work of electrical and mechanical equipment, as well as the navigation lock, and include the following works:

- Installation of new paved, metal covers for the entry of equipment, in all technological premises. It is planned to install new, prefabricated, thermally insulated covers, with all the necessary additional elements for support and fastening.
- Removal of damaged layers on walls and ceilings. Filling all cracks, painting with dispersive paint. Plastering the walls to a height of 2.2 m and laying ceramic tiles.
- Dismantling of all corrugated sheet metal coverings, as well as supporting frames made of metal profiles and installation of new metal coverings in a metal frame made of box metal profiles with anti-corrosion protection and final painting with metal paint.
- Dismantling of clinker ceramic tiles in all technological premises, the floors will be leveled with a rabbed cement screed with the necessary falls and new, clinker ceramic tiles will be installed on the appropriate glue, with the construction of a plinth.

4.2.2 Rehabilitation of constructions

As part of the rehabilitation of the ***control tower constructions***, it is necessary to perform the following works:

- repair of the supporting steel lattice of the control tower gondola (detailed inspection of all elements of the steel rod lattice, connection sheets and all connections, repair of observed damages, replacement of individual parts of the steel lattice for which inspection indicates the need for restoration and corrosion protection)
- repair of the concrete pillar of the gondola and the roof concrete slab (preparation of the surface by cleaning, sandblasting or applying high pressure jets, removal of the damaged layer of concrete if any, possible cleaning of reinforcement and repair if necessary, application of mortar on a sound surface, filling all holes in concrete at the points of the form anchoring, care of concrete surface.

As part of the construction works on the rehabilitation of the HPNS "Djerdap 2" navigation lock, the reconstruction of the ***technological and transformer rooms*** on the coastal and river side of the lock chamber is planned. Reconstruction works should include all technological rooms on the upper and lower head, rooms with transformer, diesel generator, cable and FP galleries.

EU PPF - PROJECT PREPARATION FACILITY

It is necessary to perform all necessary repairs of concrete in order to prevent leakage and wetting on the walls and ceilings of rooms and galleries by grout injection, removal of existing equipment stands and their adaptation in accordance with the requirements of new equipment and equipment manufacturer's proposal; construction of a reinforced concrete base for accommodating a diesel unit near the mixing station - left side of the lock, upstream head. Prior to the installation of the equipment, the technological premises must be repaired, arranged and cleaned.

The project of rehabilitation, adaptation and reconstruction of concrete facilities of the navigation lock envisages works for repair of identified damages on construction objects, as follows:

- Repair of damage to the concrete surfaces of the pillars and the quay wall of the upstream berthing area, damage to the concrete surfaces of the chamber and the heads of the lock, as well as damage to the concrete surfaces of the quay wall of the downstream berthing area by the method of the manual repair of the concrete.
- Repair of cracks in concrete surfaces in the chamber and in the zones of the lock's heads, concrete surfaces of the quay wall of the upstream berthing area by grout injections.
- Crystallization on the inner walls of the chamber and in the zones of the lock's heads.

4.2.3 Roads

The project includes the reconstruction of the existing internal roads on the both sides, along the lock chamber, which are defined as Road 1 and Road 2, and which are in the function of the subject system, as well as the access area to the control tower, defined as Road 3. Longitudinal and transverse cracks, rutting and potholes with a tendency of further expansion were observed on the roads.

As a proposal for the reconstruction of the subject traffic areas, it is necessary to remove existing layers of the asphalt, all to the reinforced concrete slabs or to the supporting layer of asphalt, and then do the cleaning and spraying of the concrete base with the emulsion. A polyester fiber geocomposite will be placed over the prepared surface. Then, if necessary, construct a slope layer of AB 8 in a thickness of 3 to 5 cm, and new asphalt as a final layer of AB 11 in a thickness of 5 cm.

4.2.4 Hydraulic part

The slope of the river side of the embankment in the downstream berthing area was damaged due to effect of water flow and waves during the operation of the hydroelectric power plant. The upstream spike of the embankment in the downstream berthing area is eroded and therefore it is necessary to repair the upstream spike and repair the part of the slope on the river side of the embankment of the downstream berthing area.

It is envisaged that the crown of the embankment of the downstream pre-port will be brought to the projected elevation of 40 m above sea level with the slopes of the embankment at a slope of 1: 2.5. The body of the



EU PPF - PROJECT PREPARATION FACILITY

embankment is formed of sandy-gravel material. The flattening of the embankment crown by embankment will be done up to the level of 39.5 m above sea level. The crown of the embankment will be covered with a layer of brakestone 0.5 m thick, with brakestone granulation of 31.5 - 63 mm.

The slopes of the embankment in the downstream berthing area will be protected by a stone embankment (150 - 800 mm on the part of the slope below the elevation of 36 m above sea level and 75 - 400 mm between the elevation of 36 m above sea level and the crown of the embankment). The stone cladding is laid from the level of the embankment crown - 40 m above sea level to the level of 27.2 m above sea level. A layer of stone, 1.0 m thick, is placed on a filter layer 0.5 m thick. Under the filter layer, the installation of geotextiles is envisaged as a preventive measure of protection against soil suffocation under the filter.

At the upstream end, it is projected that the embankment of the berthing area ends with a circular skittle. The lining of the stone embankment is placed on the upstream spike of the embankment and continues in the downstream direction on both sides of the embankment. On the bank side of the embankment slope, the stone embankment is placed at a length of 39 m, all the way to the pedestrian bridge zone, and on the river side, the slope of the stone embankment is placed at a length of 157 m.

Stone material for the filter layer, curtain (breakstone) and lining (stone charge) will be procured from the existing quarry "Slatina", which is located on the road to the village of Slatina.

Earthworks on the rehabilitation of the existing embankment will be performed by floating machinery.



Figure 4-2 - Embankment on the river side in the downstream berthing area at HPNS "Djerdap 2"



EU PPF - PROJECT PREPARATION FACILITY

Figure 4-3 - Upstream spike of the embankment on the river side of the downstream berthing area at HPNS "Djerdap 2"

4.2.1 Electrical power installations

The project envisages the complete **replacement of the existing 6.3 kV voltage cells** on the lower head of the navigation lock, as well as the installation of a disconnection-switching block on the 6.3 kV side of the transformer on the upper head of the navigation lock. The project also envisages the replacement of 10 kV cables..

Due to changes in the concept of electrohydraulic shutter drives, the **replacement of power transformers** with new, double-winding dry-type transformers, power 1600 kVA, transmission ratio $6.3 \pm 2 \times 2.5\% / 0.4$ kV is also planned. Transformers will be delivered and installed in appropriate factory housings. The existing transformers are dry, double-wound, with a transmission ratio of $6.3 \pm 2 \times 2.5\% / 0.4$ kV, power 1000 kVA.

The project envisages the complete **replacement of the existing 0.4 kV distribution lines**, on both navigation lock heads, as well as the power cables for the power supply of the newly designed and existing consumers, which will remain in operation even after navigation lock adaptation. The electric power equipment that is the subject of replacement includes the following: 0.4 kV main switchboard, 0.4 kV sub-distribution cabinets in all technological rooms, 0.4 kV switchboard in the control tower and power cables. The concept of basic and backup power supply of the main 0.4 kV distribution lines will be retained in the newly designed solution.

Diesel generator for power supply of the main voltage distribution of 0.4 kV system of fire protection of the navigation lock. As part of the 0.4 kV voltage works, it is necessary to move the diesel generator from the mixing station, ie install a new diesel generator, 125 kVA, container type, with associated switching equipment, to supply the fire protection system of the navigation lock, on the plateau next to the portal crane on the river side of the upper head of the lock.

The uninterruptible power supply system will meet all the requirements of specific consumers for management and telecommunications that require continuous (uninterruptible) power supply.

The uninterruptible power supply system with a voltage of 231 V and 50 Hz will be formed in the main switchboard of auxiliary voltages, which will be located in the cabin of the control tower. In normal operation, the uninterruptible power supply system will be powered via an inverter. The inverter, single-phase, static, 220V DC / 231V, 50 Hz, power 10 kVA, will be powered from the first busbar section in the main voltage distribution 220 V jss. The backup power supply of the system will be reported from the 0.4 kV main distribution on the upper head via an insulating transformer 231 V / 231 V, 50 Hz. The power of that transformer is 10 kVA and is harmonized with the maximum simultaneous power of all consumers of the system.



EU PPF - PROJECT PREPARATION FACILITY

DC power supply system. The project envisages complete replacement of DC voltage distribution equipment, as well as all cable connections. DC power will be provided at two voltage levels of 220 V DC and 24 V DC.

The project envisages testing the electrical resistance of existing installations, after which it is necessary to adapt the existing installations in order to ensure the characteristics in accordance with the applicable technical regulations. In the premises and on the parts of the cable channels in which it is necessary to dismantle the existing installations for the needs of performing construction works, the scope of works will include the installation of new equipment for these installations. In addition to measuring the total transient resistance of the earthing switch, it is planned to record the contact voltage and steps and on the basis of the measured values to propose any necessary additional measures (potential ramps, insulating bases, etc.).

The adaptation of the **control system on the navigation lock** envisages the introduction of a new, modern, distributed and hierarchically organized system with the following levels of management: level of local management (level of functional units), level of central management (control tower). From the point of view of managing the process of translating a vessel, ie in a functional sense, a navigation lock can be divided into functional units, so that each functional unit consists of individual subsystems, ie processes. The following functional units of the navigation lock are provided: upper head, lower head, auxiliary systems, supporting systems.

All planned new equipment with existing equipment that remains in operation, and which is of interest to the management system, should form a single, integrated and fully consistent system. The selected level of management must not suspend any of the protective functions implemented at any level of the management system. Malfunction or failure at a higher management level must not affect the defined operation of the lower management levels. Regardless of the level from which it is managed, all levels will have the possibility of supervision within their competencies at all times.

Auxiliary systems of the navigation lock, which are the subject of replacement within the project of adaptation, rehabilitation and reconstruction of the navigation lock at HPP "Djerdap 2", in addition to the system for powering consumers of the navigation lock with electricity include: traffic light signaling system; heating, ventilation and air conditioning system; outdoor and indoor lighting system; stable fire extinguishing system; cranes; discharge and drainage system (pumping stations); guide system and door sills; central lubrication system for working double doors.

The equipment of these systems will be replaced with new ones, which will enable the necessary functionality of the system equipment itself and the navigation lock as a whole. The equipment will be defined in accordance with the relevant standards.

Stable fire extinguishing system. The conceptual solution envisages a complete replacement of electrical equipment and installation of this system, which includes distribution cabinets, electric motor drives, measuring and signaling equipment, system management equipment, cables and cable accessories.



EU PPF - PROJECT PREPARATION FACILITY

Guide rail and door sill heating system. The designed works will include complete replacement of equipment, which includes replacement of induction heating cables (heaters), cabinets with switches to protect heaters from overload and short circuit and contactors for switching on heaters, installation cables for connecting equipment and contact thermometers for automatic on/off of the heaters. Automatic system operation is provided, depending on the measured outdoor temperature.

Cranes. The project of adaptation of the navigation lock envisages a complete replacement of the gantry cranes on the upper and lower heads, as well as the device for raising the overhaul door on the lower head. As part of the crane replacement, electrical equipment and installations will be installed on the new cranes, which will ensure reliable and safe operation of all drives.

Outdoor and indoor lighting system. The project envisages complete replacement of equipment (distribution cabinets, lamps, switches, sockets, brackets, poles) and installation (cables and cable accessories) of indoor and outdoor lighting systems. The newly designed lamps will have LED modules. In accordance with the Internal Standard for lighting of electric power plants JSC "Elektromreža Srbije" IS-EMS 314: 2014, the following types of lighting are provided for lighting of the facility NL "Djerdap 2": Basic (functional) lighting; Security lighting (anti-panic lighting); Auxiliary lighting.

The project envisages a complete **replacement of the existing equipment for heating, ventilation and air conditioning** with a new one, with the application of modern solutions related to this equipment. The electrical part includes the equipment and installations required for power supply and control of the heating and air conditioning system of technological rooms and rooms in the control tower.

Supporting systems of the navigation lock, which are the subject of replacement within the project of adaptation, rehabilitation and reconstruction of the navigation lock at HPP "Djerdap 2" are: electro-hydraulic drive of the safety net, boat mooring system, grid clogging measurement system, water level measurement system, system for measuring meteorological parameters, fire alarm system, vessel detection system, sound system, radar system, video surveillance system, radioactive radiation measurement system, conversation recording system, radio communication system, telephone system.

The equipment of these systems will be replaced with new ones, which will enable the necessary functionality of the system equipment itself and the navigation lock as a whole. The equipment will be defined in accordance with the relevant standards.

Lightning protection system. The project does not envisage works on the replacement of the lightning protection installation.

4.2.2 Mechanical installations

The hydraulic drive of doors and shutters on the upstream head of the ship navigation lock is located in two separate drive facilities on the river and shore side and includes drives for: servomotors of working doors, servomotors of emergency repair doors and servomotors of working gallery shutters. The hydraulic drive

EU PPF - PROJECT PREPARATION FACILITY

installation of the door and shutter on the downstream head of the ship's lock is located in the drive facilities on the river and coastal side and includes drives for: servomotors of working double doors and servomotors of the main gallery shutters.

Rehabilitation and adaptation of electro-hydraulic door and shutter drives envisages replacement of complete existing equipment with a new modern technical concept using modern components and in accordance with the needs of hydromechanical equipment usage after reconstruction.

Execution of works and delivery of equipment for rehabilitation, adaptation and reconstruction of electrohydraulic door and shutter drives will include the following:

- Dismantling of existing equipment and its disposal at the landfill;
- Installation of new equipment for hydraulic drive doors and shutters on the upper and lower head;
- Installation of new hydraulic units equipment in the equipment rooms and control blocks on the upper and lower head;
- Installation of new piping equipment on the upper and lower head;
- Delivery of the required amount of hydraulic oil for filling and flushing the drive system on the upper and lower head, including a reserve quantity of 20% of the quantity required for filling.
-

Hydraulic drive installations of the safety net for braking ships are located in special rooms on the river and coastal wall of the lower head of the navigation lock and include drives with hydraulic servomotors. Hydraulic brake servomotors are housed in load-bearing steel structures in the river and coastal wall of the lower head of the navigation lock.

Rehabilitation and adaptation of electro-hydraulic drives of the safety net envisages the replacement of complete existing equipment with a new, modern technical concept with the use of modern components and in accordance with the needs of hydromechanical equipment usage after reconstruction.

Execution of works and delivery of equipment for rehabilitation, adaptation and reconstruction of electrohydraulic drives of the safety net will include:

- Dismantling of existing equipment and its disposal at the landfill;
- Installation of new equipment of hydraulic cylinders for the drive of network mechanisms and shock absorption;
- Installation of new equipment of hydraulic units in equipment rooms and control blocks;
- Installation of new piping equipment;
- Delivery of the required amount of hydraulic oil for filling and rinsing the drive system, including a reserve quantity of 20% of the quantity required for filling.

Main operating door on the upstream head

The main operating door is a flat sliding door, located on the chamber of the upstream head of the navigation lock, with a clear opening of 34 x 17 m. It is used to close or open the upstream chamber of the lock when the vessel enters the chamber from the upstream pre-port and vice versa. The door is driven by two hydraulic servomotors, which are connected to the side consoles on the door.



EU PPF - PROJECT PREPARATION FACILITY

Repairment and adaptation of the hydromechanical equipment of the operating door on the upstream head envisages the replacement of the door construction and the examination of the condition with the repair of the determined damages on the concrete parts. Execution works and delivery of equipment for rehabilitation, adaptation and reconstruction of operating doors of the upstream head will include:

- Dismantling of existing equipment and its disposal at the landfill;
- Sandblasting, non-destructive testing and repair of concrete parts including necessary construction works and anti-corrosion protection;
- New operating doors with associated mechanical parts;
- New sealing set of working doors;
- New connections between the service door to the drive servomotor, including connecting elements.

Working double-leaf door downstream head

On the downstream head there is an operating double door (34 x 17 m), hydraulically operated and used to close and open the chamber and maintain the water level in the chamber. With the repair and adaptation of the hydromechanical equipment of the working double-leaf doors on the downstream head, it is planned to examine the condition and repair the determined damage to the door with the replacement of wearing parts.

The new operating door will be designed for an elevation of normal deceleration of 41.25 m above sea level. The door will be made of welded steel construction using modern materials in order to increase the quality of new equipment.

After works completion on testing and repairing, the renewal of anticorrosion protection will be performed, whereby the mentioned works will also include surface sandblasting. The concrete surfaces parts in contact with the door seals will be metallized with stainless steel or stainless steel strips will be welded. The scope of replacement of parts for working double-leaf doors will include bearings and complete sealing set, as well as timber on the downstream side of each leaf.

Safety net for braking ships

In front of the lower head, there is a system with a net for braking ships in case of an emergency situation when the ship move towards the double-leaf doors on the lower head, while entering into the chamber during the downstream navigation. It is composed of steel ropes with drive servomotors. The drive servomotors are housed in load-bearing steel structures in the river and coastal wall of the downstream head of the navigation lock.

With the repairment and adaptation of the hydromechanical equipment of the safety net, it is planned to examine the condition and to repair the determined damages. Rehabilitation and adaptation of hydromechanical equipment of the safety net will include the following:

- Dismantling of existing equipment and its disposal for the needs of reconstruction works;
- Sandblasting of steel structure of beams and concreted parts;
- Non-destructive testing of steel structure of beams, associated mechanical parts, mesh and concreted parts;



EU PPF - PROJECT PREPARATION FACILITY

- Testing the network with a test load;
- Repair of damage determined by testing, including necessary construction works and corrosion protection;
- Replacement of mechanical parts on the steel structure of the beam, which will necessarily include all bearings..

Entrance griting

At the water entrance into the gallery of the upstream head, ie. at the water intake, gratings were placed, two pieces, on each water intake, dimensions 4.5 x 4.5 m. Rehabilitation and adaptation of hydromechanical equipment envisages replacement of existing entrance gratings. The gratings will be made of welded steel construction using modern materials in order to increase the quality of equipment and safety and security at work. The design of the new gratings will be adapted for installation in existing niches with concrete parts.

The installation of new gratings will be preceded by sandblasting, non-destructive testing and repair of concrete parts, including necessary construction works and corrosion protection.

Heating and ventilation system

Each of the technological rooms of the navigation lock on the upper and lower head is equipped with its own heating and ventilation system which provides the minimum allowed room temperature (10 °C), as well as the required amount of fresh air.

The rehabilitation and adaptation of the mechanical equipment of the air conditioning and ventilation system includes the complete replacement of the existing mechanical equipment for heating and ventilation of the operating rooms on the upper and lower head and the gallery rooms at elevations of + 37.50 and + 40.30 m. Existing equipment is being replaced with modern devices, with the same characteristics and appropriate safety measures.

The project solution for the adaptation of heating and ventilation of the control tower will include air conditioning of the control room, technical room, room with electrical cabinets and entrance to the gondola via a heat pump with heat recovery in the "split" version. The project solution will include forced ventilation of all rooms in the control tower via a duct recuperator as well as heating of toilets and stairs via a modern electric boiler of 70 kW, hot water radiators and pipes that will run inside the gondola.

Cranes

To service the equipment of the upstream head, a portal crane with a load capacity of 400 kN and a span of 7.5 m has been installed on the coastal side, which is used for manipulating equipment in the drive room, and for manipulating equipment and installations necessary for gallery operation. To service the upstream head equipment, a portal crane with a load capacity of 400 kN and a span of 7.5 m has been installed on the river side, which is used for manipulating equipment in the drive room, as well as for manipulating equipment and installations necessary for gallery operation. To service the downstream head equipment, a portal crane with



EU PPF - PROJECT PREPARATION FACILITY

a load capacity of 400 kN and a span of 12 m has been installed on the river side, which is used for manipulating the equipment in the drive room, as well as for manipulating the equipment and installations necessary for gallery operation. The drive rooms on the river and coastal side of the upstream head are equipped with one bridge crane with a load capacity of 20 kN and a span of 5.7 m. The drive room on the coastal side of the downstream head is equipped with a bridge crane with a load capacity of 20 kN and a span of 5 m. The drive room on the river side of the lower head is equipped with one bridge crane with a load capacity of 20 kN and a span of 7.5 m. The pumping station for emptying and drainage on the river side of the downstream head is equipped with one bridge crane with a load capacity of 80 kN and a range of 5.0 m.

With the rehabilitation and adaptation of the cranes on the navigation lock, the replacement of the existing equipment is planned. Existing crane tracks and bumpers for portal and bridge cranes will be inspected and any identified damage will be repaired. In addition, the renewal of anti-corrosion protection is planned.

Discharge and drainage system

One **pumping station for emptying and drainage** is planned on the river wall of the upstream head of the navigation lock and one on a coastal wall of the upstream head of the navigation lock. The function of each of the pumping stations is as follows: emptying the niche of emergency-overhaul and operating doors, emptying the space between the overhaul gallery shutters, drainage of the room at elevation 37.5 m and 34.3 m, drainage of the pipeline gallery on the coast, drainage of the cable gallery on the river side and drainage of the manhole of the shutter.

Rehabilitation and adaptation of the drainage and drainage system at the navigation lock means the replacement of the existing equipment in the pumping pools, pumping stations, shafts and shutters on the upstream and downstream head of the lock.

The existing equipment of the drainage and discharge system will be dismantled and replaced with a new one of the same basic technical characteristics with the application of modern design, components and materials in order to increase the quality of equipment and safety and security at work. Auxiliary equipment for access to the main equipment of the drainage and discharge system consisting of access platforms, climbers and fences, as well as concreted parts of the pipeline will be subject to inspection and repair or replacement in accordance with the condition determined by the inspection.

Automatic lubrication system for working double gates

For automatic lubrication of wing bearings and drive servomotors of working gate, a central lubrication system is installed on the river and coastal side of the downstream head of the lock. One device located in the room of the appropriate drive servomotor is provided for lubrication of the bearing of the coastal and river wing of the working door on the downstream head of the conductor. The distribution of the grease pipe from the



EU PPF - PROJECT PREPARATION FACILITY

lubrication device to the grease points on the door is performed through the gallery in the niche of each door leaf.

Rehabilitation and adaptation of the central lubrication system of double working gate envisages dismantling of existing equipment and replacement with a new of the same basic technical characteristics with the application of modern design, components and materials in order to increase the quality of equipment and safety and security at work. The new equipment of the lubrication system will be adjusted to the technical solution of the installation of new drive servomotors and reconstructed assemblies of working double gate envisaged in other parts of the machine design.

Stable fire extinguishing system

Stable fire protection system consists of: pumping station for water pumping from wells, pumped water tank, pipe water supply from the tank to the navigation lock, pipe water distribution along the walls of the lock chamber, storage and preparation system of foam extract, foam extract distribution along the walls of the lock, Venturi mixers in the places of monitors, the monitors along the walls of the chamber, the fire protection control system in the control tower.

Rehabilitation and adaptation of the mechanical equipment of the stable fire extinguishing system includes the replacement of the existing valve equipment in the shut-off of the pumped water tank and of the complete equipment on the lock. The equipment that is the subject of replacement will be dismantled and replaced with a new one of the same basic technical characteristics by applying modern design, components and materials in order to increase the quality of equipment and safety and security at work. In addition to the new equipment, the delivery of the required amount of foaming extract is also planned.



EU PPF - PROJECT PREPARATION FACILITY

5 OVERVIEW OF MAIN ALTERNATIVES CONSIDERED BY THE PROJECT HOLDER

Within the project of adaptation of the navigation locks, no alternative solutions were considered. Given the type and scope of interventions (replacement of equipment) on the planned adaptation, it was not applicable to consider alternative solutions, but the timely replacement of worn-out and unreliable equipment that calls into question the continued functioning of the navigation locks.

EU PPF - PROJECT PREPARATION FACILITY

6 DESCRIPTION OF THE ENVIRONMENT CONDITIONS

Air quality

The territory of the municipality of Negotin is not covered by the national network of automatic stations for air quality monitoring. The examination of air quality in the summer and winter period is performed by the Institute for Public Health "Timok" from Zajecar. An apparatus for sampling sulfur dioxide, soot and sediment was installed in JNA Street No. 10 in Negotin (8 km by air from the navigation lock). According to the data on the results of air quality monitoring published on the website of the Municipality of Negotin, the measured values were within the limit values or slightly deviated from them.

Surface water quality

The Serbian Environmental Protection Agency (SEPA) is the official institution for providing data on the quality of surface and groundwater and river sediments in the Republic of Serbia, as well as on the quality of other environmental medium, starting in 2011.

Monitoring of the quality of the Danube River is performed at a total of nine stations, of which Brza Palanka and Radujevac are the closest to HPP "Djerdap 2". Brza Palanka is located about 21 kilometers upstream, and Radujevac 10 kilometers downstream from the navigation lock. At both measuring stations, monthly monitoring of general parameters, oxygen regime, nutrients, salinity, metals, microbiological parameters and priority and priority hazardous substances is performed.

By the Decree on the categorization of watercourses ("Official Gazette of the SRS" No. 5/1968), the Danube River, throughout its course through the Republic of Serbia, is classified in the II category. According to the Regulation on Water Classification ("Official Gazette of the SRS" No. 5/1968), class II includes waters that are suitable for bathing; recreation and water sports, for the cultivation of less noble species of fish (cyprinids), as well as waters that can be used with normal methods of processing (coagulation, filtration and disinfection) to supply the settlement with drinking water and in the food industry.

The results of analyzes of surface water samples (watercourses), ie the relevant values of parameters for the annual period, were compared with the limit values of quality classes prescribed by the Regulation on limit values of pollutants in surface and ground waters and sediments, and deadlines for achieving them ("Official Gazette of RS" No. 50/2012).

The values of priority and priority hazardous substances are compared with the values of environmental quality standards (EQS), ie annual average value (AA-EQS) and maximum allowable concentration (MAC-EQS), prescribed by the Regulation on limit values of priority and priority hazardous substances that pollute the surface waters and deadlines for their achievement ("Official Gazette of RS", No. 24/2014). To determine the quality class, the criteria prescribed by the Regulation ("Official Gazette of RS" No. 50/2012) were used.

EU PPF - PROJECT PREPARATION FACILITY

According to the results of surface and groundwater quality testing for 2017, 2018 and 2019, the tested parameters at both measuring stations mostly corresponded to categories I and II. Deviations from the prescribed category of the Danube River, during the mentioned three years and at both measuring stations, were in terms of nutrient concentration (nitrogen and phosphorus compounds), total iron and microbiological parameters. Also, the presence of dissolved nickel and fluoranthene in concentrations corresponding to categories III/IV was determined.

The following table provides an overview of the parameters that deviated from the prescribed category of the Danube River.

Table 6.1 – Danube water quality in 2017, 2018 and 2019 - an overview of parameters that deviated from the prescribed category

Year	Measuring station	Deviations from category II
2017.	Brza Palanka	Total nitrogen (III) Iron, total (III)
	Radujevac	Total nitrogen (III) Nitrites (III) Total phosphorus (III) Iron, total (III) Number of aerobic heterotrophs (III) Nickel dissolved 1x (III/IV)
2018.	Brza Palanka	Dissolved oxygen (III) Total coliforms Number of aerobic heterotrophs (III) Fluoranthene 1x (III / IV)
	Radujevac	Dissolved oxygen (III) Total phosphorus (III) Orthophosphates (III) Fluoranthene 1x (III / IV)
2019.	Brza Palanka	Number of aerobic heterotrophs (III) Fluoranthene 1x (III/IV)
	Radujevac	Iron, total (III) Number of aerobic heterotrophs (III) Nickel dissolved 1x (III/IV)

Sediment

The publication "Quality of river sediment and accumulations of Serbia", issued by the Serbian Environmental Protection Agency in 2019, contains the results of testing the quality of river sediments and accumulations from the annual surface water monitoring programs for the period from 2012 to 2017. The sediment samples



EU PPF - PROJECT PREPARATION FACILITY

were tested for heavy metals (zinc, copper, chromium, lead, cadmium, mercury, nickel, arsenic) and organic pollutants (polycyclic aromatic hydrocarbons (PAH), polychlorinated biphenyls (PCBs), organochlorine pesticides and triacin-based pesticides).

The results of the analysis of heavy metals show that at the sampling point in Brza Palanka, the limit values were not exceeded, while in the samples from the Radujevac measuring station, the values for copper and nickel were exceeded.

Of the tested organic pollutants, the content of p,p'-DDE on the profiles Brza Palanka (2.6 µg/kg) and Radujevac (1.7 µg/kg) indicate that the maximum allowed concentrations have been exceeded.

Land quality

On the territory of the municipality of Negotin, systematic examinations of soil quality are not performed. The land is more or less degraded by various natural and anthropogenic processes. Anthropogenic soil pollution originates from the chemical industry from which powdery substances are emitted into the air, which are later deposited on the soil, as well as from the dispersal of pyrite burn from the landfill in Prahovo and the seepage of atmospheric water from the phosphogypsum landfill.

The assessment of the land quality in the area of Negotin was performed in 2005, within the project "Control of fertility and determination of the contents of dangerous and harmful substances in the soils of the Republic of Serbia". It was determined that the limit values of nickel were exceeded in most of the samples. Copper concentrations were increased in three samples and cadmium in one.



EU PPF - PROJECT PREPARATION FACILITY

7 DESCRIPTION OF POSSIBLE SIGNIFICANT EFFECTS OF THE PROJECT ON THE ENVIRONMENT

The effects of revitalization of the navigation lock on the environment can be considered through two phases:

- project implementation phase, ie. work on the revitalization of the navigation lock and
- exploitation phase after the completion of project works.

Impact due to the construction works

During the works on the rehabilitation, adaptation and reconstruction of the navigation lock, there will be environmental impacts that are mostly temporary and limited to the immediate environment. Impacts occur as a consequence of the presence of people, the use of machinery, the methodology of work and last as long as the work lasts. With the cessation of works, the influences also cease. During the execution of works, there will be impacts on air quality, surface waters, soil quality, river sediment quality, noise and vibration levels, population health and the ecosystem.

Impacts of the project during the execution of works on air quality – emissions of dust, exhaust gases from engaged construction machinery and vehicles, emissions of dust during embankment of stone and installation of gravel on the crown of the embankment in the downstream pre-port, emissions of vapors from volatile organic compounds contained in anti-corrosion protection agents.

Impact of the project during the execution of works on the quality of surface waters - During the implementation of the project, there may be a negative impact on the water quality in the Danube and the lock chamber due to: works on the rehabilitation of concrete surfaces when using special high-quality concrete, penetrating crystallization material and modern materials based on polyurethane, cleaning concrete surfaces and metal structures from rust, dust, oil and other impurities by brushing, sandblasting or applying compressed air, using coatings to protect metal surfaces from corrosion (primer and anti-corrosion protection) and final paints, leakage of hydraulic oil from replaced elements of electro-hydraulic door and shutter drive equipment, works on the reconstruction and rehabilitation of the embankment in the downstream berthing area, leakage of waste hazardous materials (machine oil, fuel) from construction machinery and means of transport on the shore and from construction machinery.

Impacts of the project during the execution of works on the quality of the land - Impacts during the execution of works on the land can occur due to: the formation of temporary landfills on the ground, the formation of temporary warehouses of construction materials during the adaptation, permanent disposal of waste, leakage of harmful substances, ie. oils and fuels from construction machinery, which is in operation on the coast, by taking up space for the needs of the construction site.

Impacts of the project during the execution of works on the quality of river sediment - The change in the quality of river sediment can be caused by presence of building material residues (special concretes, epoxy resins, penetrating materials and polyurethane-based materials) and steel material (parts of metal structures



EU PPF - PROJECT PREPARATION FACILITY

and their waste during operation), used during revitalization of building structures, leakage of hazardous waste (machine oil, fuel) from navigable construction machinery.

Impacts of the project during the execution of works on the level of noise and vibration - Noise emissions will occur during construction and ground equipment works. The noise will have the greatest negative effects on the construction site of the navigation lock and in its immediate vicinity, and it is of a temporary nature.

Impacts of the project during the execution of works on the health of the population - No direct impact of the revitalization works on the health of the surrounding population is expected.

Impacts of the project during the execution of works on the ecosystem - Before the beginning of revitalization, for the needs of opening the construction site, the existing vegetation and the reproductive layer of the soil are removed from the soil surface.

Influences during the operation of the navigation lock

The realization of the planned works will not lead to a change in the purpose and function, or the way the navigation lock works. The impacts will remain the same as before the project, with the new equipment leading to greater safety at work and reducing the possibility of unwanted accidents that could have negative impacts on the environment.

EU PPF - PROJECT PREPARATION FACILITY

8 ENVIRONMENTAL IMPACT ASSESSMENT IN CASES OF ACCIDENTS

The most significant possible accident situations are:

- Leakage of oil and/or derivatives from a damaged vessel;
- Fire on the vessel and in the lock chamber;
- Discharge of hazardous water-soluble substances from the damaged vessel.

In addition to the above-mentioned accident situations, smaller-scale accident situations may also occur on the project, such as:

- leakage of oil and oil derivatives from construction machinery engaged on concrete facilities of the navigation lock,
- oil leaks when replacing equipment or from replaced equipment,
- leakage of temporarily stored hazardous substances.

During the works on the rehabilitation, adaptation and reconstruction of the navigation lock, the navigation lock will be closed for crossing and the chamber will be emptied. If a accident situation occurs and oil and/or oil derivatives are spilled from the mechanization tank into the navigation lock chamber, it will not reach the surface water but will be collected by adsorption means.

Smaller accidents (oil leaks from the tanks of vehicles) are also possible on roads and manipulative surfaces around the navigation lock, and their impact is limited to the concrete surfaces of the ship from which leaked substances can be collected. Accidental leaks due to damage to the packaging are possible in the storage of chemicals (fuels, oils and lubricants, paints and other substances).

Pollution of surface waters and land from the state road, class IIa, no. 168, connection with the state road 35 - Dušanovac - state border with Romania (border crossing Kusjak), is also possible because all the waste generated during the reconstruction of the navigation lock will be transported via it, so any accident in this sector of the road will adversely affect on the soil around the navigation lock, which is sloping towards the Danube and possibly to groundwater.

Accident situations on engaged navigational machinery can lead to surface water pollution.

The accident situations that may occur during the operation of the project will remain the same as during the existing operation of the navigation lock, namely oil spills and oil derivatives, fire and explosions due to the presence of a large amount of hydrocarbons.

The occurrence of fires on vessels in the navigation lock can most often occur during the passage of tank ships transporting large quantities of oil and derivatives, when due to unfavorable conditions there is increased evaporation and formation of clouds of flammable and explosive vapors in the lock chambers. After the revitalization of the navigation lock, an identical concept of the existing fire protection will be used. The revitalization of the navigation lock includes the replacement of the existing fire extinguishing equipment with



EU PPF - PROJECT PREPARATION FACILITY

new ones, as well as fire alarm signals, which enables a quick response. When a fire occurs on board, the revitalized fire protection system enables the fire to be alarmed in an appropriate manner and the successful extinguishing of the fire that may occur in the lock chamber.

The consequences of the accident depend on the place of origin, type and amount of spilled substance, its physical-chemical and toxicological characteristics, meteorological and hydrological conditions, preventive measures taken, as well as the speed and efficiency of intervention of the vessel's crew and competent HPP services.

Taking into account the quantities of substances transported through the navigation lock and the frequency of transport, it is most likely that oil and/or oil derivatives will spill. The spill in the lock chamber also increases the danger of fire, so the spill of hydrocarbons and fire are the two most significant possible accidents during the operation of the navigation lock.

The following hazardous substances will be present during the project:

- petroleum and petroleum products in construction machinery, vehicles and vessels,
- lubricants in the equipment of the navigation lock which is subject to replacement.

Oil is a thick and viscous liquid, poorly soluble in water. When oil reaches the surface of the water, it forms an oil slick, after which various processes appear, the intensity of which is influenced by the physico-chemical characteristics of the oil itself, ie. its derivatives, climatic conditions, hydrological conditions, etc. The main processes that contribute to the decomposition of oil in water or on water surfaces are: evaporation, dissolution, emulsification, dispersion, precipitation, oxidation and microbiological degradation.

Under the influence of external factors, lighter fractions evaporate (with a lower boiling point), the density of oil increases and it sinks to the bottom.

The dissolution of oil in water is very weak and is limited to lighter fractions. The emulsifying mechanism results in the formation of a stable emulsion known as "chocolate moss". Emulsification slows down the decomposition of oil due to less exposure of oil to water and air.

Dispersion mechanically or chemically contributes to the increase of surface pollution and its penetration into underground layers. It selectively affects the solubility of the oil by increasing the surface area of the oil spill and thus increasing the solubility of the low molecular weight components.

Oil deposition occurs as a consequence of oil aging, which results in an increase in the density of the spilled oil. When the density of the oil becomes higher than the density of the water, the oil will sink. The oil can also sink if it has previously been adsorbed on heavy particles of sand and silt.

Polycyclic aromatic hydrocarbons have the property of concentrating on suspended particles of organic matter. The sorption process is influenced by the mineral composition of the soil, temperature, pH and the

EU PPF - PROJECT PREPARATION FACILITY

characteristics of the compound itself. Sorption is most intense on particles of sand, clay and organic matter, which is related to the size and structure of these particles.

Analysis of the probability of accident situations

According to the Rulebook on the content of the accident prevention policy and the content and methodology of drafting the Safety Report and the Accident Protection Plan ("Official Gazette of RS", No. 41/2010), the risk of a chemical accident is assessed on the basis of the probability of an accident and the extent of the possible consequences.

The probability of an accident is expressed numerically or descriptively as small, medium and large, and the consequences as small, significant, serious, large and catastrophic.

Depending on the probability of an accident and the consequences that would occur, the risk of a chemical accident is defined as: negligible, small, medium, large and very large risk, according to the criteria shown in the following table.

Table 8.1 - Risk criteria based on the probability of an accident and possible consequences

Probability of an accident	Consequences				
	small	significant	serious	large	catastrophic
Low	negligible risk	low risk	medium risk	high risk	very high risk*
Medium	low risk	medium risk	high risk	very high risk*	very high risk*
High	medium risk	high risk	very high risk*	very high risk*	very high risk*

* risk is not acceptable

Risk is acceptable if it is assessed as: negligible, low, medium and high risk. Acceptable risk can be managed under certain conditions, prescribed regulations and a defined course of action when performing hazardous activities.

At the shipyard of HPP "Djerdap 2", the two most unfavorable scenarios of possible accidents are large spills from a thin vessel and a fire on the vessel. According to domestic and world experiences, the probability of these accidents is very low.

The assessment of possible consequences was performed on the basis of an analysis of events according to the criteria of the Rulebook on the content of accident prevention policy and the content and methodology of the Safety Report and Accident Protection Plan ("Official Gazette of RS", No. 41/2010) and is shown in the following table.

Table 8.2 - Risk assessment for the navigation lock HPP "Djerdap 2"

Type of accident	Probability of occurrence	Consequences	Risk assessment
Large spills from a tank vessel	low	significant	low
Fire on the vessel	Low	significant	low



EU PPF - PROJECT PREPARATION FACILITY

The possible level of accidents is determined based on the width of the vulnerable zone and vulnerability analysis. In the chamber, the level of accidents is assessed as the level I of accidents - the level of dangerous plants where the consequences of the accident are limited to part of the plant (installation) or the whole plant, at the same time there are no consequences for the whole complex, because the water area is completely closed.

In berthing areas, the level of accidents is assessed as II level of accidents - the level of the complex where the consequences of the accident are limited to part or whole complex, at the same time there are no consequences outside the boundaries of the complex. No major impact on the Danube river is expected, due to the existence of a floating dam and equipment for collecting spilled derivatives. The accident will have no effect on the Romanian side of the Danube.

EU PPF - PROJECT PREPARATION FACILITY

9 TRANSBOUNDARY ENVIRONMENTAL IMPACT

As a signatory to the ESPOO Convention (Law on Ratification of the Convention on Environmental Impact Assessment in a Transboundary Context, "Official Gazette of RS - International Agreements", No. 102/2007) and the Kiev Protocol (Law on Ratification of the Kyoto Protocol to the United Nations Framework Convention on Change climate, "Official Gazette of RS", No. 88/2007 and 38/2009), as well as international agreements related to the conservation of migratory species (Law on Ratification of the Convention on the Conservation of Migratory Species of Wild Animals, "Official Gazette of RS - International Agreements", No. 102/2007); and other international agreements; The Republic of Serbia has undertaken to inform other countries regarding projects that may have a transboundary impact.

In 2018, Serbia also adopted the Law on Ratification of the Multilateral agreement among the countries of south-eastern Europe for implementation of the Convention on Environmental Impact Assessment in a Transboundary Context ("Official Gazette. RS Gazette", no. 12/18), made on 20th of May 2008 in Bucharest.

The Espoo Convention defines transboundary impact as: "any impact, not only of a global nature, within an area under the jurisdiction of a Party, which causes a proposed activity whose physical origin is wholly or partly wholly or partly within an area under the jurisdiction of the other Party".

The analysis of the project and its environmental impacts did not identify possible transboundary environmental impacts of the project. During the works, if there are accidental oil leaks from the vessels engaged in the reconstruction and rehabilitation of embankments or concrete structures in the berthing areas, the leaked contents will be collected by floating dams and other equipment for repairing the spill owned by HPP "Djerdap 2". HPP "Djerdap 2" has adopted procedures, a trained team and equipment for reacting in case of accidents, so if an accident occurred, the pollution would be contained and remediated with a quick reaction.

Minor pollution with suspended matter that will occur due to the works on the embankment will be maintained first along the right bank, and then it will be diluted very quickly due to the huge flow.

The planned works on the rehabilitation, adaptation and reconstruction of the navigation lock HPP "Djerdap 2" will not have any effect on the environment of Romania, ie on the quality of air, water, population, phytocenoses present in Romania, as well as on ichthyofauna and other environmental factors.

EU PPF - PROJECT PREPARATION FACILITY

10 DESCRIPTION OF MEASURES PROVIDED TO PREVENT, REDUCE AND ELIMINATE SIGNIFICANT ADVERSE IMPACTS

Necessary measures to reduce or prevent adverse impacts can be systematized into the following categories:

- Protection measures provided by law and other regulations, norms and standards and deadlines for their achievement
- Protection measures provided by the technical documentation and conditions of the competent authorities and organizations
- Protection measures during project construction
- Protection measures during the regular operation of the project
- Protection measures in case of an accident
- Protection measures in case of cessation and decommissioning of the project.

Protection measures provided by law and other regulations, norms and standards and deadlines for their achievement

The measures provided by laws and other regulations include the application of norms and standards in the selection and acquiring of devices and equipment for the proposed technological process, as well as those technical measures according to which the collection of all waste materials will be performed.

Air protection measures will be in accordance with the Law on Air Protection ("Official Gazette of RS", No. 36/09 and 10/13) and accompanying bylaws.

Water protection measures will be in accordance with the Law on Waters ("Official Gazette of RS", No. 30/10, 93/2012, 101/2016, 95/2018 and 95/2018 - other law) and accompanying bylaws .

Soil protection measures will be in accordance with the Law on Soil Protection ("Official Gazette of RS", No. 112/15) and accompanying bylaws.

Noise protection measures will be in accordance with the Law on Environmental Noise Protection ("Official Gazette of RS", No. 36/09, 88/10) and accompanying bylaws.

The treatment of waste materials will be in accordance with the Law on Waste Management ("Official Gazette of the RS", No. 36/2009, 88/2010, 14/2016 and 95/2018 - other law) and the accompanying bylaws.

In addition to these legal acts, during operation, it is necessary to comply with regulations in the field of environmental protection, which relate to environmental protection, nature protection, protection against non-ionizing and ionizing radiation, fire protection, transport of hazardous cargo, planning and construction, as well as laws governing labour and occupational health and safety and others.

EU PPF - PROJECT PREPARATION FACILITY

The contractor is obliged to comply with all applicable legal regulations in the field of occupational health and safety during the execution of works.

Protection measures during the execution of works

Air quality protection measures

Reducing the impact of emissions of harmful gases and dust on air quality will be reduced by applying the following measures:

- Limiting the number and area of locations where works are performed as well as the duration of works;
- Daily cleaning of access roads near the site (removal of soil and sand) to prevent the formation of dust;
- Daily cleaning of manipulative and work surfaces from construction waste. After demolition and removal of unusable material (rubble, etc.), the construction site must be clean, orderly and ready for performing new works;
- Controlling the scattering of loose materials from vehicles and at the location for storage of excavated material;
- Proper selection of construction machinery and vehicles for the procurement of modern devices with the lowest exhaust emissions;
- Monitoring and maintaining the condition of the engines and machinery, in order to eliminate excessive exhaust emissions,
- Shutting down the engine when machinery and vehicles are not in use.

Water quality protection measures

- Controlled disposal of waste from vessels, which perform works on the revitalization of the ship's lock:
 - collection and treatment of sanitary, ballast and bilge wastewater from vessels;
 - prevention of uncontrolled disposal of solid waste from vessels and collection in local containers on vessels, and then disposal of their contents in containers of municipal waste on the shore;
 - monitoring and maintaining the condition of vessels and their engines, in order to prevent oil and fuel leaks;
- Regular maintenance and control of the condition of construction machines and engines, in order to eliminate the possibility of oil, derivatives and machine oil getting into the water;
- Collection of sanitary wastewater from staff accommodation facilities (offices, workshops, warehouses) in an impermeable septic tank, with the necessary emptying of the tanks of the competent utility service, as well as cleaning and removal after completion of works;



EU PPF - PROJECT PREPARATION FACILITY

- Controlled use of special materials for repair of concrete structures (high-quality concrete, epoxy resins, penetrating material and modern materials based on polyurethane) in all respects



EU PPF - PROJECT PREPARATION FACILITY

according to the requirements of the manufacturers of these materials and technical conditions for execution;

- Use of quality crushed stone without admixture of soil material, in order to reduce the concentration of suspended matter in the river environment and perform rip-rap protection of the upstream pre-port according to the technical conditions for execution;
- Controlled manipulation of construction machinery, in order to reduce petroleum products on concrete surfaces of the ship's lock structure and oiling of atmospheric water;
- Removal of waste generated during the cleaning of surfaces of metal structures and concreted parts from paint and corrosion residues, as well as during sandblasting of metal surfaces and transportation of waste to the appropriate landfill;
- Controlled use of the most environmentally friendly coatings and final paints for protection of metal surfaces from corrosion according to the requirements of the manufacturers of these materials and technical conditions for execution;
- Performing oil change in the complete revitalized system of electrohydraulic drive of doors and shutters in accordance with the existing rules for oil handling at HPP "Djerdap 2" with maximum protection measures against any leakage into the environment;

Soil quality protection measures

- Equip the construction site with appropriate housing containers for workers, sanitary facilities for personal hygiene and chemical mobile toilets, in accordance with the number of employees;
- Classify materials during demolition or dismantling according to the type and dimensions, clean and store them in a temporary storage within the construction site until they are handed over to the authorized operator for its disposal;
- Collect solid municipal and construction waste in special containers;
- Recyclable waste (metal, wood, glass, plastic) must be collected separately and properly disposed of until handed over to a person authorized or licensed to manage these types of waste;
- Provide a sufficient number of marked dedicated containers, tanks and barrels for various types of solid and liquid hazardous waste, generated during the reconstruction of the lock;
- Perform regular maintenance and control of the condition of the engines of construction machines and means of transport, in order to prevent the ingress of oil, petroleum products and machine oil into the soil and groundwater;
- It is forbidden to pour oil from construction machines and trucks or their repair at the location in question during the previous works and the execution of works on the reconstruction of the ship's lock facilities;
- Define the characteristics of the sorbent that will be used when spilling small quantities of oil and petroleum products, motor oil, hydraulic oil, paints, etc. as well as the method of application, collection and procedure with the collected sorbent;
- Provide on-site sorbent containers and containers for disposal of used sorbent;



EU PPF - PROJECT PREPARATION FACILITY

- In case of spillage of hazardous substances, remove the layer of contaminated soil, replacing the soil brought from another location, analysis of soil samples and disposal in accordance with the results of the analysis;
- In case of major discharges of oil and petroleum products and other hazardous substances into the soil, perform soil testing, delineation of contaminated soil and, if the tests determine the need, remediation of contaminated soil according to the project approved by the competent Ministry;
- Store petroleum products in tanks with a double mantle or with a secondary containment, and/or in barrels with a secondary containment. The secondary containment is selected so that it can contain the entire volume of liquid from the tank in the event of a leak;
- Transshipment of petroleum products: fuels, oils and lubricants, as well as servicing of construction machinery and vehicles should be performed exclusively on concrete watertight surfaces, which have a controlled drainage system for evacuation of waste and wastewater with an oil separator;
- Transport of petroleum products and hydraulic oil to be performed by certified means of transport with the provision of constant supervision during the transport and use of these materials;
- Provision of a sufficient number of special, mobile containers, according to the number of permanent and temporary workers for the collection of solid municipal waste from the location of revitalization and delivery to the municipal landfill in agreement with the competent municipal service of the city.
- Concreting the surface of the base of the landfill of waste steel material in order to prevent the leakage of oil from discarded mechanical and electrical equipment into the underground environment;
- Leaked, used and waste oils, oiled items, waste steel materials and other waste materials generated during the revitalization of the ship's lock, which have the character of hazardous waste



EU PPF - PROJECT PREPARATION FACILITY

or may be hazardous waste, will be temporarily stored on covered concrete substrates with built drainage system for evacuation of waste and wastewater with oil separator;

- Temporarily dispose of electrical and electronic waste on concrete surfaces and in metal containers intended for their storage;
- For permanent waste disposal, sign contracts with operators who have permits for permanent care/disposal of a given type of waste;
- Upon completion of the reconstruction, carry out landscaping and horticultural arranging of the construction site in the ship's locks complex with a combination of indigenous deciduous trees, conifers and ornamental shrubs in accordance with a Special project.

River sediment quality protection measures

- Controlled use of special materials for the repair of concrete structures, in compliance with the technical conditions for construction;
- Controlled cleaning of metal surfaces and transportation of generated waste to the appropriate landfill;
- Use of the most environmentally friendly anti-corrosion agents.

Noise and vibration protection measures

- Proper selection of construction machines and vehicles in order to acquire modern devices with the lowest noise emission and the least vibration during operation;
- Regular maintenance of machinery in good condition, in order to minimize noise and vibration;
- Shutting down the engine of the machine when it is not in use.

Ecosystem protection measures

- There will be no unnecessary removal of vegetation and felling of trees on the construction site and in the surroundings and which will be formed on the bank of the Danube;
- After the completion of the works, the location of the ship's lock and temporary construction site will be rehabilitated by removing temporary structures, objects and materials from the surfaces



EU PPF - PROJECT PREPARATION FACILITY

used for the works, transporting them to the selected landfill, mechanical and biological soil reclamation, planting grass, shrubs and long-term afforestation.

Other protection measures

- Development of the Main design of the construction organization which should be in accordance with the safety and other rules of HPP "Djerdap 2".
- The contractor is obliged to comply with the relevant provisions of applicable national rulebooks and regulations when performing the works;
- Execution of preparatory works, securing the location of the lock and the coastal area of the construction site and performing other works that secure the immediate environment, life and health of people and safe traffic before the start of revitalization of the lock;
- Fencing and proper marking of the location of execution of works;
- Disposal of removed humus for later use for horticultural landscaping;
- Prevention of significant change in the morphology of the surrounding terrain during the revitalization works;
- Provide an adequate place for storage (landfill) of materials used during the works on the complex;
- Store all construction and other materials that may contaminate the environment (various insulation materials, bitumens, etc.) on the construction site, in closed facilities, with a watertight floor that can be cleaned;
- Comply with all regulations on safety and security at work and prevent any adverse impacts on the environment and the immediate environment of the site;
- Construction rubble, where there is dusty crushed material, cover with foil in order to reduce the possibility of raising dust due to wind;
- In case of high speed wind and "critical" directions, temporarily stop the works.
- Carry out regular wetting of dusty surfaces and prevent scattering of construction materials during transport, by covering the materials and regulating the speed of vehicles;
- It is necessary to provide sand, zeolite or other sorbent on the construction site in case of spillage of harmful substances (petroleum products, oils, chemicals, etc.);
- It is not allowed to perform mechanical service of machines on the construction site;
- In case of liquid and other materials (oil derivatives, oils, chemicals, etc.) leaking onto the free surface, first take all measures to prevent further leakage, and then sprinkle the place with sand,

EU PPF - PROJECT PREPARATION FACILITY

zeolite or other sorbent. Dispose of the contaminated sorbent in special containers and ensure its collection through an authorized operator;

- Train and educate employees working on the construction site for efficient implementation of all environmental protection measures. This especially refers to the use and maintenance of construction machinery, waste management, etc.
- Ensure safe disposal of the excavation from the embankment and its removal to precisely defined places on the site or to the city landfill;
- Collect all packaging made of hazardous material and dispose of it in containers for storage of hazardous waste and hand it over to authorized operators for disposal;
- Separate waste by type and store it separately;
- Provision of appropriate personal protective equipment for employees on revitalization, prescribed by the Law on Occupational Health and Safety ("Official Gazette of the Republic of Serbia" No. 101/05, 91/151 and 113/17 - other law).

Protection measures during the regular operation of the project

Independently of the works on the revitalization of the ship's lock, HPP "Djerap 2" regularly implements basic environmental protection measures during the operation of the ship's lock:

- ensuring the permanent functionality of the facility,
- regular maintenance of the facility to prevent possible damage,
- implementation of control of condition of all installations of installed equipment,
- monitoring of all environmental parameters that may be disturbed due to the existence and functioning of the facility.

The project of revitalization of building structures, mechanical and electrical equipment and installation of equipment and installations plans the reconstruction of damaged parts of the lock, as well as the revitalization of complete electrical-mechanical equipment so that it can work reliably and unobstructed in the next project period of 30 years. It is also planned to introduce modern lock management.

The applied technical solutions have maximally improved the functioning of the existing ship's lock facility, so that the exploitation of the revitalized facility does not cause an increase in negative environmental impacts compared to the existing facility. On the contrary, the installation of modern mechanical and electrical equipment largely eliminates the negative impact on the environment. The situation is identical with accidental impacts on the environment.

Protection measures in case of an accident

Organizational protection measures



EU PPF - PROJECT PREPARATION FACILITY

In accordance with the Law on Disaster Risk Reduction and Emergency Management ("Official Gazette of RS", No. 87/18), the Regulation on the content, manner of preparation and obligations of entities related to the preparation of disaster risk assessment and protection and rescue plans ("Official Gazette of RS", No. 102/20) and the Instruction on the Methodology of preparation and content of disaster risk assessment and protection and rescue plan ("Official Gazette of RS", No. 80/19), HPP "Djerdap 2", as a subject of special importance for the economy of the Republic of Serbia in the field of energy and transport, it has the obligation to prepare a Disaster Risk Assessment and a Protection and Rescue Plan.

Disaster risk assessment identifies the type, character and origin of individual disaster risks, the degree of endangerment, factors that cause or increase the degree of possible danger, consequences that may occur on human life and health, the environment, material and cultural goods, as well as other assumptions relevant to the conduct of normal life, economic and social activities. Disaster risk assessment includes:

- a. identification of disaster hazards (natural disasters and technical-technological accidents);
- b. disaster scenarios;
- c. the level of risk, which includes the assessment of the probability of the event, the protected value and the assessment of the consequences for the protected value.

The Protection and Rescue Plan plans measures and activities for prevention and mitigation of the consequences of disasters, strengths and resources of the subjects of disaster risk reduction and emergency management, their organized and coordinated engagement and action in emergencies to protect and rescue people, material and cultural goods and providing basic living conditions. The plan for protection and rescue of entities of special importance, which includes HPP "Djerdap 2", contains the following elements in particular:

- a. early warning and preparedness;
- b. execution of tasks determined by the National Plan (Protection and Rescue Plan of the Republic of Serbia):
 - a. review of obtained tasks,
 - b. review of measures and activities on the implementation of the obtained tasks,
 - c. list of employees who are engaged in the execution of the obtained tasks,
 - d. review of material and technical means that are engaged in the implementation of the obtained tasks,
 - e. activation plan,
 - f. excerpt from the review of companies and other legal entities with which it cooperates in the execution of the obtained tasks;



EU PPF - PROJECT PREPARATION FACILITY

- 3) civil protection measures - protection and rescue of employees and users of services of entities of special importance for protection and rescue, as follows:
 - a. alerting,
 - b. evacuation,
 - c. removing,
 - d. care for the endangered and injured,
 - e. first aid,
 - f. review of means for personal and mutual and collective protection.

The National Protection and Rescue Plan contains all the necessary elements for protection and rescue in emergency situations, in particular::

- 1) early warning and preparedness (readiness);
- 2) mobilization and activation;
- 3) protection and rescue by types of identified hazards from the Assessment;
- 4) civil protection measures:
 - g. evacuation,
 - h. care for the endangered and injured,
 - i. first and medical aid,
 - j. sanitation,
 - k. use of forces and subjects of protection and rescue.

Soil protection measures

These measures provide protection of the soil both in minor accidents and in accident situations.

1. Generated solid potentially hazardous waste (oiled equipment, contaminated soil, used sorbent for oil substances, sand and paint after sandblasting, packaging of paint and protective agents, sludge from separators, etc.) classify and collect it in appropriate containers and perform waste characterization;
2. Dispose of liquid hazardous waste (oily water, hydraulic fluid, used motor and hydraulic oils, as well as lubricants, etc.) in tanks and certified, marked metal barrels with lids and perform characterization;
3. It is forbidden to mix different types of waste and joint storage of incompatible types of waste;
4. Manipulation and temporary storage of collected potentially hazardous and liquid waste should be performed on a covered, impermeable substrate, resistant to stored waste, and equipped with a secondary containment (parapet around the substrate or tank) that can collect liquid matter in case of packaging damage, or on an impermeable substrate with built technological sewerage connected to the oil and grease separator;
5. To harmonize the further procedure with solid and liquid hazardous waste with the results of waste characterization, and to entrust the collection and final disposal to a legal entity (authorized operator) that has a permit for the management of the specified types of waste;
6. Visit the temporary waste storage site on a daily basis in order to timely identify packaging damage and leaks if they occur;



EU PPF - PROJECT PREPARATION FACILITY

7. Transshipment of petroleum products: fuels, oils and lubricants, as well as servicing of construction machines and vehicles should be performed exclusively on concrete watertight surfaces, which have a controlled drainage system for evacuation of waste and wastewater with an oil separator;
8. Use construction machines and means of transport that have passed technical inspections on the construction site;
9. Perform regular maintenance and control of the condition of construction machinery and means of transport;
10. Determine the type of sorbent that will be used for spilling small quantities of oil and petroleum products, motor oil, hydraulic oil, paints, etc. as well as the method of application, collection and procedure with the collected sorbent;
11. Provide on the construction site containers with sorbent and containers for temporary disposal of used sorbent;
12. In case of soil pollution, perform soil testing, delineating of the contaminated land and, if necessary, remediation of the soil according to the reclamation and remediation project to which the consent of the competent Ministry has been obtained.

Surface and groundwater and sediment protection measures

Protection of the aquatic environment from pollution in accident situations is extremely important for the living world of the Danube, due to the possible volume of pollution and negative consequences, and it is one of the obligations assumed by international conventions and agreements.

Water can be polluted directly by discharging pollutants into it or indirectly through soil pollution.

Direct pollution of surface waters and sediments occurs during minor or major accidents on vessels or machines engaged in the reconstruction of the lock, which result in direct spillage of oil and / or petroleum products into the aquatic environment. The protection measures in this case are, as in any similar accident:

- The ship's lock must have a floating barrier, a suitable vessel, chemical means and equipment for collecting, temporarily storing and neutralizing any leaked oil and/or petroleum products in the chambers and pre-ports;
- If it is determined at the pre-ports that oil, petroleum and/or derivatives are leaking from one of the vessels and water pollution occurs, a floating dam must be installed immediately;
- It is necessary to urgently eliminate the malfunction or damage to the vessel that led to the accident, in order to stop further pollution of the aquatic environment;



EU PPF - PROJECT PREPARATION FACILITY

- The vessel from which the petroleum, petroleum products or oil leaked must not leave the area enclosed by the floating dam, until the pollution is picked up by appropriate equipment and means;
- Collect spilled petroleum products from the surface of the water mirror with the help of special traps and pump oily water and petroleum products into special tanks/containers;
- To dispose of this type of waste, hire a legal entity authorized to handle this type of hazardous waste.

Indirect protection of surface and groundwater and sediment is performed by applying soil protection measures. The application of soil protection measures reduces or eliminates soil pollution, but also potential water and sediment pollution that occurs through the transport of pollution from soil to groundwater, and due to the connection of groundwater and surface water, transport of pollution into surface water, and/or leaching of contaminated soil into watercourse.

Fire protection measures

- Ship's lock HPP "Djerdap 2" is equipped with an automatic fire alarm system consisting of a fire alarm control panel, manual fire detectors, automatic fire detectors, alarm sirens, parallel display boards and other accessories and equipment;
- The ship's lock chamber is completely covered by a stable fire extinguishing system: a system of nozzles to protect the lock door and monitors along the walls of the chamber, while the fire on the vessel is extinguished by the equipment of each ship separately;
- During the reconstruction of the lock, the complete mechanical and electrical equipment and installations of the fire protection system will be completely replaced, which provides additional safety and ensures maximum reliability of the revitalized fire protection system;
- The fire control unit is located in the control tower and is connected to the SCADA system of the lock, ie a single system for monitoring and control;
- Continuous operation of the SCADA system for monitoring and remote control of the FP system from the command tower;
- Constant human presence next to the SCADA system;
- Alarms are performed via conventional alarm sirens distributed throughout the building, and are activated selectively by fire alarm sectors;
- Extinguishing fires in the lock chambers is done with monitors evenly distributed along the wall of the ship's chamber, with water or a mixture of water and foam extract;
- It is necessary to constantly maintain the pumping station "Kusjak", water tank, venturi mixer, tank for storage of extract and monitors in functional condition;
- It is necessary to have a permanent water reserve in the tank of the "Kusjak" system;
- It is necessary to provide a sufficient amount of foam extract in the foam extract storage tanks;
- Hand-held fire extinguishers are also envisaged as fire-fighting measures in the event of a fire in the lock's facilities (command tower, technological rooms);



EU PPF - PROJECT PREPARATION FACILITY

- In case of fire, the following should be done: start extinguishing the fire, stop the endangered device and turn off the electricity, report the fire to the security/fire brigade, take all measures to prevent the spread of fire to neighboring facilities - devices, initiate evacuation of people from the endangered area.

Envisaged measures in case of an accident

- It is obligatory to provide a certain amount of sorbents on the construction site in case of leakage of fuel and lubricants from construction machines and means of transport;
- In case of spillage, leakage of petroleum, petroleum products, oil, as an accident that can occur in all phases of realization and regular operation of the lock, it is necessary to immediately start remediation of the terrain at the location, and the waste generated by remediation should be packed in impermeable barrels with lids;
- Carry out the characterization of waste generated by the collection of spilled petroleum, oil, lubricants, or other hazardous substances and hand it over to an authorized operator who has a permit to manage a given type of waste for further disposal, with mandatory records on waste collection;
- Use correct, regularly maintained mechanization and means of transport that have passed technical inspections on the construction site;
- Use proper sailing machinery for water works;
- In case of chemical leaks, accident response includes: notifying the responsible person, putting on protective equipment, taking care of the injured (if any), preventing further leaks and spilling of chemicals, collecting chemicals and packaging as hazardous waste, remediation of contaminated sites;
- In the event of a petroleum and petroleum products leak in the ship's lock chamber or in the pre-ports, install a floating dam and collect the leaked contents;
- All places where the accident occurred must be repaired and completely repaired as soon as possible;
- When reacting in case of a hazard, it is mandatory to use adequate protective equipment (protective suit, shoes, goggles, gloves, masks);
- Rescue and first aid actions include: rescue (general), rescue from the hazard of suffocation by inhalation of gases, intoxication caused by inhalation of gas;
- After the accident, the project holder is obliged to immediately, and no later than within 24 hours, inform the competent body of the competent ministry about the emergency event; The notification contains information on the circumstances of the emergency, location, time, imminent danger to human health and a description of the measures taken.

EU PPF - PROJECT PREPARATION FACILITY

11 ENVIRONMENTAL IMPACT MONITORING PROGRAM

Monitoring of the impact on the environment is done in order to timely detect the negative impact of activities on the environment. Impact assessment enables timely response and application of additional measures in order to prevent or reduce negative impacts to a minimum.

Based on the defined possible impacts of the project on the environment, the parameters for monitoring the impact of the project on the environment are defined.

Monitoring of environmental impact is performed by an authorized organization, accredited according to the standard for sampling, measurement, analysis of the observed parameter. Selected organizations should have accreditations for the parameters covered by the monitoring and the authorization of the competent ministry.

11.1 Overview of the state of the environment before the start of the operation of the project at locations where the impact on the environment is expected

Chapter 5 analyzes the current state of the environment, i.e. the situation before the start of the project.

11.2 Parameters on the basis of which harmful effects on the environment can be determined

Surface water quality monitoring parameters

Surface water quality monitoring parameters were selected to include possible impacts on water quality during the works on the revitalization of the HPP "Djerdap 2", as well as possible impacts during the operation of the navigation lock.

Monitoring parameters would be: temperature, electrical conductivity, pH, suspended solids, sedimentary substances, dissolved oxygen concentration, % oxygen saturation, BOD₅, chemical oxygen demand (KMnO₄), chemical oxygen demand (K₂Cr₂O₇), petroleum hydrocarbons, arsenic, zinc, chromium, iron, lead, nickel, cadmium, mercury.

Surface water quality monitoring parameters and their limit values by classes are defined by the Decree on limit values of pollutants in surface and ground waters and sediment and deadlines for their achievement ("Official Gazette of RS", No. 50/2012), Decree on limit values of priority and priority hazardous substances that pollute surface waters and deadlines for their achievement ("Official Gazette of RS", No. 24/2014), Regulation on hazardous substances in waters ("Official Gazette of SRS", No. 31/82).

According to the Decree on the categorization of watercourses ("Official Gazette of RS", No. 5/68), the Danube from the Hungarian border to the Bulgarian border belongs to the II category, i.e. the II water class.



EU PPF - PROJECT PREPARATION FACILITY

The following table shows the parameters of the water quality of the Danube River that need to be monitored in order to determine the impact of the execution of works on the project and the operation of the navigation lock on the environment.

Table 11.1 - Danube water quality monitoring parameters

Parameter	Unit	Limit values Class II	Average annual concentration
Temperature	°C	/	/
Electrical conductivity	mS/cm	1000*	/
pH	/	6.5-8.5*	/
Suspended matter	mg/l	25*	/
Dissolved oxygen	mgO ₂ /l	7.0*	/
Oxygen saturation	%		/
- epilimnion (stratified water)		70-90*	/
- hypolimnion (stratified water)		50-70*	/
- unstratified water		50-70*	/
BOD ₅	mgO ₂ /l	5.0*	/
COD (K ₂ Cr ₂ O ₇)	mgO ₂ /l	15*	/
COD (KMnO ₄)	mgO ₂ /l	10*	/
Petroleum hydrocarbons		(1) *	/
Arsenic	µg/l	10*	/
Boron	µg/l	1000*	/
Copper	µg/l	5 (T=10)* 22 (T=50)* 40 (T=100)* 112 (T=300)*	/
Zinc	µg/l	300 (T=10)* 700 (T=50)* 1000 (T=100)* 2000 (T=500)*	/
Chromium hexavalent	µg/l	100***	/
Chromium trivalent	µg/l	100***	/
Iron (total)	µg/l	300***	/
Lead	µg/l	14**	1.2 **
Nickel	µg/l	34**	4 *
Cadmium	µg/l	0.45**	0.08 **
Mercury	µg/l	0.07**	/

* the Decree on limit values of pollutants in surface and ground waters and sediment and deadlines for their achievement ("Official Gazette of RS", No. 50/2012)

** Decree on limit values of priority and priority hazardous substances that pollute surface waters and deadlines for their achievement ("Official Gazette of RS", No. 24/2014)

*** Regulation on hazardous substances in waters ("Official Gazette of SRS", No. 31/82)

T – Water hardness (mg/l CaCO₃)



EU PPF - PROJECT PREPARATION FACILITY

- (1) Petroleum products must not be present in water in such quantities that:
- form a visible film on the surface of water or coatings on the banks of watercourses and lakes,
 - give a distinctive "hydrocarbon" taste to fish,
 - cause harmful effects in fish

Sediment quality monitoring parameters

The parameters of sediment quality monitoring, their limit values and sediment classification are defined by the Decree on limit values of pollutants in surface and groundwater and sediment and deadlines for their achievement ("Official Gazette of RS", No. 50/2012).

The following table shows the parameters that need to be monitored in the sediment to assess the status and trend of sediment quality.

Table 11.2 - Limit values for assessment of sediment status and trend

Parameter	Unit	Target value	Maximum allowable concentration	Remediation value
Arsenic (As)	mg/kg	29	42	55
Cadmium (Cd)	mg/kg	0.8	6.4	12
Chrome (Cr)	mg/kg	100	240	380
Copper (Cu)	mg/kg	36	110	190
Mercury (Hg)	mg/kg	0.3	1.6	10
Lead (Pb)	mg/kg	85	310	530
Nickel (Ni)	mg/kg	35	44	210
Zinc (Zn)	mg/kg	140	430	720
Mineral oils	mg/kg	50	3000	5000
Polycyclic Aromatic Hydrocarbons (PAH) ⁽¹⁾	mg/kg	1	10	40
Anthracene	mg/kg	0.001	0.1	/
Naphthalene	mg/kg	0.001	0.1	/
Phenanthrene	mg/kg	0.005	0.5	/
Fluoranthenes	mg/kg	0.03	3	/
Benzo (a) anthracene	mg/kg	0.003	0.4	/
Kryzene	mg/kg	0.1	11	/
Benzo (k) fluoranthene	mg/kg	0.02	2	/
Benzo (a) pyrene	mg/kg	0.003	3	/
Benzo (g, h, i) perylene	mg/kg	0.08	8	/
Indeno (1,2,3-cd) pyrene	mg/kg	0.06	6	/

⁽¹⁾ the parameter refers to the sum of the following compounds: naphthalene, anthracene, phenanthrene, fluoranthene, benzo (a) anthracene, kryzene, benzo (k) fluoranthene, benzo (a) pyrene, benzo (g, h, i) perylene, indeno (1, 2,3-cd) pyrene



EU PPF - PROJECT PREPARATION FACILITY

The limit values for metals and organic matter refer to standard sediment containing 10% organic matter and 25% clay.

In case of changes in existing or adoption of new regulations governing the area of sediment quality the monitoring of sediment quality will be adjusted to the applicable regulations.

Soil and groundwater monitoring parameters

Monitoring of soil and groundwater is performed according to the Decree on limit values of polluting, harmful and dangerous substances in the soil ("Official Gazette of RS", No. 30/18 and 64/19). Parameters for monitoring the quality of soil and groundwater would be: groundwater level, electrical conductivity, pH, dissolved oxygen concentration, % oxygen saturation, BOD₅, chemical oxygen demand (KMnO₄), chemical oxygen demand (K₂Cr₂O₇), benzene, ethylbenzene, toluene, xylenes, phenol, cresols (total), PAH (total), total petroleum hydrocarbons (fractions C₆ – C₄₀), arsenic, copper, zinc, chromium, iron, manganese, lead, nickel, cadmium, mercury.

The limit values and remediation values for metals and arsenic, with the exception of antimony, molybdenum, selenium, tellurium, thallium and silver, depend on the content of clay and organic matter in the soil.

The following table shows the parameters that need to be monitored in the soil and groundwater to assess the impact of the execution of works on project and the operation of the navigation lock on the environment.

Table 11.3 - Soil and groundwater quality parameters

Parameter	Soil (mg/kg of absolutely dry matter)		Aquifer (µg/l in solution)
	Limit maximum value	Remediation value	Remediation value
Arsenic (As)	42	55	60
Cadmium (Cd)	29	55	6
Chrome (Cr)	100	380	30
Copper (Cu)	36	190	75
Mercury (Hg)	0.3	10	0.3
Lead (Pb)	85	530	75
Nickel (Ni)	35	210	75
Zinc (Zn)	140	720	800
Total petroleum hydrocarbons C ₆ -C ₄₀	50	5000	600
Polycyclic Aromatic Hydrocarbons (PAH) - Total ⁽¹⁾	1	40	/
Anthracene	/	/	5
Naphthalene	/	/	70



EU PPF - PROJECT PREPARATION FACILITY

Parameter	Soil (mg/kg of absolutely dry matter)		Aquifer (µg/l in solution)
	Limit maximum value	Remediation value	Remediation value
Phenanthrene	/	/	5
Fluoranthenes	/	/	1
Benzo (a) anthracene	/	/	0.5
Kryzen	/	/	0.2
Benzo (k) fluoranthene	/	/	0.05
Benzo (a) pyrene	/	/	0.05
Benzo (g. h. i) perylene	/	/	0.05
Indeno (1.2.3-cd) pyrene	/	/	0.05

⁽¹⁾ the parameter refers to the sum of the following compounds: naphthalene, anthracene, phenanthrene, fluoranthene, benzo (a) anthracene, kryzene, benzo (k) fluoranthene, benzo (a) pyrene, benzo (g, h, i) perylene, indeno (1, 2,3-cd) pyrene

Location, manner and frequency of determined parameters monitoring

Surface waters

During the execution of works on the project, conduct monitoring once a month at the following three locations:

- at the entrance to the upstream berthing area of HPP "Djerdap 2",
- downstream berthing area
- lock chamber.

Analysis of water in the lock chamber should be performed when the chamber is filled with water.

During the navigation lock operation, the surface water quality monitoring should be performed quarterly at two measuring points:

- at the entrance of the upstream berthing area of HP Djerdap 2,
- downstream berthing area.

Sediment quality monitoring

Sediment quality monitoring should be performed after the completion of all planned works on the project. Quality monitoring should be performed at three locations in the downstream berthing area. Two sampling locations should be on the ships route through the berthing area; one at the entrance to the berthing area and the other in the middle of the road through the downstream berthing area. The third location should be perpendicular to the second location, but closer to the shore.



EU PPF - PROJECT PREPARATION FACILITY

These locations should be maintained during further monitoring of the navigation lock operation because it will enable sediment quality control both on the route by which ships move through the ports, where due to the passage of ships less sediment deposition, and in the area near the coast where the impact of ship passage is less pronounced. so the sediment deposition is higher.

After the completion of works on the adaptation of the lock and the planned monitoring of the impact of the project on the quality of sediment, further control of the impact of navigation lock on the quality of sediment should be performed once a year during low waters. Another point that would be located in the upper berthing area, approximately in the middle of ship route through the upstream berthing area, should be included in the monitoring.

Monitoring the project impact on soil and groundwater quality

Monitoring the project impact on soil and groundwater quality should be done through groundwater monitoring. For monitoring purposes, it is necessary to install a piezometric well between the construction site and the Danube bank.

Groundwater levels monitoring should be carried out once a week, while testing of other required parameters should be performed before the start of preparatory work and then once every three months.

The piezometer should be installed before the work starts, because it is necessary to perform soil and groundwater sampling in order to determine the baseline.

Table 11.1 - Monitoring program during construction and operation work of the navigation lock at HPP "Djerdap 2"

Environmental factor	Parameter	During construction work		During operation work	
		Sampling location	Sampling frequency	Sampling location	Sampling frequency
Danube river	See Table 11.1	at the entrance to the upstream berthing area	Once a month	at the entrance to the upstream berthing area	4 times annually
		downstream berthing area		downstream berthing area	
		lock chamber		/	
Danube river sediment	See Table 11.2	at the entrance to the downstream berthing area	After the completion of works	at the entrance to the downstream berthing area	one a year during small waters
		in the middle of the route through the downstream berthing area		in the middle of the route through the downstream berthing area	
		in the middle of the route through the downstream berthing area, closer to the shore		in the middle of the route through the downstream berthing area, closer to the shore	
Soil	See Table 11.3.	At the piezometer drilling site - between the	Before the works start and in case of soil pollution	/	/



EU PPF - PROJECT PREPARATION FACILITY

		construction site and the Danube River			
Groundwater	See Table 11.3	On the piezometer between the construction site and the Danube River	Before the start of works, and then once in three months	On the piezometer between the construction site and the Danube river	once a year during dry season




EU PPF - PROJECT PREPARATION FACILITY

12 DATA ON TECHNICAL DEFICIENCIES


During the preparation of the Environmental Impact Assessment Study of the navigation lock adaptation project within HPNS "Djerdap 2", the multidisciplinary team that participated in the preparation did not encounter any special difficulties or shortcomings that are important for the quality of the Study.




Annex 1. Layout of navigation lock of HPP "Djerdap 2"



Osnova na koti 64.85



Presek 1-1




Vera B. Slović

R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR REPUBLIKA SRBIJA - MGSJ / JP "ELEKTROPRIVREDA SRBIJE"		PROJEKAT IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVODNICE HE "ĐERDAP 2"	
OBJEKAT BRODSKA PREVODNICA HE "ĐERDAP 2"		CRTEŽ DJERDAP 2 KOMANDNI TORANJ - OSNOVA I PRESEK	
BROJ UGOVORA 18072-204	DATUM 10.2019.	FAZA IDP	
ODG. PROJEKTANT Vera Slović, dipl.inž.grad.	UN. KONTROLA Tamara Šumar, dipl.inž.grad.	GL. PROJEKTANT Todora Lazić, dipl.inž.el.	RJ 110-202
RAZMERA 1:50		LISTOVA 1	LIST 1
DEO PROJEKTA 2/1		ŠIFRA CRTEŽA 18072-IDP-II-01.1-202-01	BR.CRTEŽA/IZMENA 01


Scale 1:100




Situacija gornje glave O.S nivo. 43.50 (1:200)





Poprecni presek A - A' (1:200)



Izgled teh. prostorije i trafo prostorije nivo. 37.50 (1:200)



Izgled na koti 34.30




Pozicija soba u sistemu - HEPS Djerdap 2




Pen Culić

R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR REPUBLIKA SRBIJA - MGSJ / JP "ELEKTROPRIVREDA SRBIJE"		PROJEKAT IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVODNICE HE "ĐERDAP 2"	
OBJEKAT BRODSKA PREVODNICA HE "ĐERDAP 2"		CRTEŽ DJERDAP 2 GORNJA GLAVA - OBALNA STRANA TEHN. PROSTORIJA - SITUACIJA POSTOJEĆE STANJE	
BROJ UGOVORA 18072-204	DATUM 10.2019.	FAZA IDP	
ODG. PROJEKTANT Vera Slović, dipl.inž.grad.	UN. KONTROLA Tamara Šumar, dipl.inž.grad.	GL. PROJEKTANT Todora Lazić, dipl.inž.el.	RJ 110-202
		RAZMERA 1:50	LISTOVA 1
		DEO PROJEKTA ŠIFRA CRTEŽA 2/2 18072-IDP-II-01.2-202-01	LIST 1 BR.CRTEŽA/IZMENA 01


Situacija gornje glave O.S nivo. 43.50 (1:200)




Poprečni presek A - A' (1:200)




Izgled prostorija na koti 34.30 (1:400)




Izgled sobe sa dizel gen.kota 37.50 (1:200)



Izgled teh. prostorije i prostorije sa dizel agregatom nivo. 37.50 (1:200)



Pozicija soba u sistemu - HEPS Djerdap 2




Željko Čulić

R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR REPUBLIKA SRBIJA - MGSJ / JP "ELEKTROPRIVREDA SRBIJE"		PROJEKAT IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVODNICE HE "ĐERDAP 2"	
OBJEKAT BRODSKA PREVODNICA HE "ĐERDAP 2"		CRTEŽ DJERDAP 2 GORNJA GLAVA - REČNA STRANA TEHN. PROSTORIJA - SITUACIJA	
BROJ UGOVORA 18072-204	DATUM 10.2019.	FAZA IDP	
ODG. PROJEKTANT Vera Slović, dipl.inž.građ.	UN. KONTROLA Tamara Šumar, dipl.inž.građ.	GL. PROJEKTANT Todora Lazić, dipl.inž.el.	RJ 110-202
			RAZMERA 1:50
			LISTOVA 1
			DEO PROJEKTA ŠIFRA CRTEŽA BR.CRTEŽA/IZMENA
			2/2 18072-IDP-II-01.2-202-02 02


A ↙

Situacija donje glave O.S. el. 43.50




A' ↙


Situacija teh. prostorija O.S. el. 37.50



Situacija teh. prostorija O.S. el. 34.50




Poprečni presek A - A'




Vera B. Slović

R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR REPUBLIKA SRBIJA - MGSJ / JP "ELEKTROPRIVREDA SRBIJE"		PROJEKAT IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVODNICE HE "ĐERDAP 2"	
OBJEKAT BRODSKA PREVODNICA HE "ĐERDAP 2"		CRTEŽ DJERDAP 2 DONJA GLAVA - OBALNA STRANA TEHN. PROSTORIJA - SITUACIJA POSTOJEĆE STANJE - ZAVRŠNI RADOVI	
BROJ UGOVORA 18072-204	DATUM 10.2019.	FAZA IDP	
ODG. PROJEKTANT Vera Slović, dipl.inž.građ.	UN. KONTROLA Tamara Šumar, dipl.inž.građ.	GL. PROJEKTANT Todora Lazić, dipl.inž.el.	RJ 110-202
RAZMERA 1:50		LISTOVA 1	LIST 1
DEO PROJEKTA 2/2		ŠIFRA CRTEŽA 18072-IDP-II-01.2-202-03	BR.CRTEŽA/IZMENA 03



Situacija donje glave, teh.prostorije sa opremom kota. 43.50




Poprecni presek A - A'



Izgled tehnoloskih prostorija na koti 37.50





Osnova na koti .34.30



Vera B. Slović



R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR REPUBLIKA SRBIJA - MGSJ / JP "ELEKTROPRIVREDA SRBIJE "		PROJEKAT IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVODNICE HE "ĐERDAP 2"	
OBJEKAT BRODSKA PREVODNICA HE "ĐERDAP 2"		CRTEŽ DJERDAP 2 DONJA GLAVA - REČNA STRANA TEHN. PROSTORIJA - SITUACIJA POSTOJEĆE STANJE - ZAVRŠNI RADOVI	
BROJ UGOVORA 18072-204	DATUM 10.2019.	FAZA IDP	
ODG. PROJEKTANT Vera Slović, dipl.inž.građ.	UN. KONTROLA Tamara Šumar, dipl.inž.građ.	GL. PROJEKTANT Todora Lazić, dipl.inž.el.	RJ 110-202 RAZMERA 1:50 LISTOVA 1 LIST 1 DEO PROJEKTA ŠIFRA CRTEŽA BR.CRTEŽA/IZMENA 2/2 18072-IDP-II-01.2-202-04 04



- Legenda**
- 1:00 x 0,25m Metoda A - Rucna sanacija
 - Farbanje ograde



R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR	REPUBLIKA SRBIJA - MGSJ / JP "ELEKTROPRIVREDA SRBIJE"		PROJEKAT
OBJEKAT	BRODSKA PREVODNICA HE "ĐERDAP 2"		IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVODNICE HE "ĐERDAP 2"
BROJ UGOVORA	DATUM	FAZA	CRTEŽ
18072-204	10.2019.	IDP	ĐERDAP 2 NIZVODNO PREDPRISTANIŠTE - REČNA STRANA SITUACIJA - PREGLED POVRŠINA KOJE TREBA TRETIRATI
ODG. PROJEKTANT	Vera Slović, dipl.inž.grad.	RJ	RAZMERA
UN. KONTROLA	Tamara Šumar, dipl.inž.grad.	110-202	LISTOVA
GL. PROJEKTANT	Todora Lazić, dipl.inž.el.	BEO PROJEKTA	LIST
		SIFRA CRTEŽA	1
		BR. CRTEŽAZIMENA	05
		2/3	18072-IDP-II-01.3-202-05




Legenda

- Metoda A - Rucna sanacija
- Farbanje ograde


Napomena: Kuke i bitve nisu u razmeri

R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR	REPUBLIKA SRBIJA - MGSJ / JP "ELEKTROPRIVREDA SRBIJE"	PROJEKAT	IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVODNICE HE "ĐERDAP 2"
OBJEKAT	BRODSKA PREVODNICA HE "ĐERDAP 2"	CRTEŽ	DJERDAP 2 NIZVODNO PREDPRISTANIŠTE - OBALNA STRANA SITUACIJA - PREGLED POVRŠINA KOJE TREBA TRETIRATI
BROJ UGOVORA	18072-204	DATUM	10.2019.
ODG. PROJEKTANT	Vera Slović, dipl.inž.grad.	FAZA	IDP
UN. KONTROLA	Tamara Šumar, dipl.inž.grad.	RJ	110-202
GL. PROJEKTANT	Todora Lazić, dipl.inž.el.	RAZMERA	LISTOVA 1
		DEO PROJEKTA	SIFRA CRTEŽA
		BR. CRTEŽAZIMENA	LIST 1
			BR. CRTEŽAZIMENA
			06


Uzvodno predpristanište - Obalna strana



Situacija prevodnice na HE Djerdap 2



Podužni presek A-A'




Podužni presek A-A'

- Legenda
- Metoda A - Rucna sanacija
 - Farbanje ograde






Per Culić


Osnova uzvodnog predpristaništa



R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR	REPUBLIKA SRBIJA - MGSJ / JP "ELEKTROPRIVREDA SRBIJE"		PROJEKAT
OBJEKAT	BRODSKA PREVODNICA HE "DĀRDAP 2"		IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVODNICE HE "DĀRDAP 2"
BROJ UGOVORA	DATUM	FAZA	CRTEŽ
18072-204	10.2019.	IDP	DĀRDAP 2
ODG. PROJEKTANT	Vera Slović, dipl.inž.grad.	RJ	UZVODNO PREDPRISTANIŠTE
UN. KONTROLA	Tamara Šumar, dipl.inž.grad.	110-202	- OBALNA STRANA
GL. PROJEKTANT	Todora Lazić, dipl.inž.el.	BEO PROJEKTA	SITUACIJA - PREGLED POVRŠINA KOJE TREBA TRETIRATI
		SIFRA CRTEŽA	LIST
		2/3	1
		18072-IDP-II-01.3-202-01	BR. CRTEŽAZIMENA
			01



Situacija prevodnice na HE Djerdap 2




Legenda

- Metoda A - Rucna sanacija
- Metoda B - Injektiranje pukotina
- Farbanje ograde




R. BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR REPUBLIKA SRBIJA - MGSI / JP "ELEKTROPRIVREDA SRBIJE "		PROJEKAT IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVODNICE HE "ĐERDAP 2"	
OBJEKAT BRODSKA PREVODNICA HE "ĐERDAP 2"		CRTEŽ DJERDAP 2 UZVODNO PREDPRISTANIŠTE - REČNA STRANA SITUACIJA - PREGLED POVRŠINA KOJE TREBA TRETIRATI	
BROJ UGOVORA 18072-204	DATUM 10.2019.	FAZA IDP	
ODG. PROJEKTANT Vera Slović, dipl.inž.grad.	RJ 110-202	RAZMERA	LISTOVA 1
UN. KONTROLA Tamara Šumar, dipl.inž.grad.	DEO PROJEKTA SIFRA CRTEŽA	LIST 1	BR. CRTEŽA/IZMENA 1
GL. PROJEKTANT Todorica Lazić, dipl.inž.el.	2/3	18072-IDP-II-01.3-202-02	02


Brodaska prevodnica HE Djerdap 2 - Osnova komore



Podužni presek A-A' - Obalna strana



Situacija prevodnice na HE Djerdap 2




Legenda

- Metoda A - Rucna sanacija
- Metoda B - Injektiranje pukotina
- Farbanje ograde




R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR	REPUBLIKA SRBIJA - MGSJ / JP "ELEKTROPRIVREDA SRBIJE"		PROJEKAT IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVODNICE HE "DJDAP 2"
OBJEKAT	BRODSKA PREVODNICA HE "DJDAP 2"		CRTEŽ DJDAP 2 KOMORA PREVODNICE - OBALNA STRANA SITUACIJA - PREGLED POVRŠINA KOJE TREBA TRETIRATI
BROJ UGOVORA	DATUM	FAZA	
18072-204	10.2019.	IDP	
ODG. PROJEKTANT	Vera Slović, dipl.inž.grad.		RJ 110-202 RAZMERA LISTOVA 1
UN. KONTROLA	Tamara Šumar, dipl.inž.grad.		LIST 1
GL. PROJEKTANT	Todora Lazić, dipl.inž.el.		BEO PROJEKTA ŠIFRA CRTEŽA BR. CRTEŽAZIMENA
	2/3	18072-IDP-II-01.3-202-03	03

Brodsko prevođnica HE Djerđap 2 - Osnova komore




Situacija prevođnice na HE Djerđap 2





Legenda

- Metoda A - Rucna sanacija
- Metoda B - Injektiranje pukotina
- Farbanje ograde

Podužni presek A-A' - Rečna strana





R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR REPUBLIKA SRBIJA - MGSJ / JP "ELEKTROPRIVREDA SRBIJE"		PROJEKAT IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVOĐNICE HE "DJEKĐAP 2"	
OBJEKAT BRODSKA PREVOĐNICA HE "DJEKĐAP 2"		CRTEŽ DJEKĐAP 2 KOMORA PREVOĐNICE - REČNA STRANA SITUACIJA - PREGLED POVRŠINA KOJE TREBA TRETIRATI	
BROJ UGOVORA 18072-204	DATUM 10.2019.	FAZA IDP	RZ 110-202
ODG. PROJEKTANT Vera Slović, dipl.inž.grad.	UN. KONTROLA Tamara Šumar, dipl.inž.grad.	BEO PROJEKTA SIFRA CRTEŽA 2/3	LISTOVA 1 LIST 1 BR. CRTEŽA IZMENA 04
GL. PROJEKTANT Todor Lazić, dipl.inž.el.	DIO PROJEKTA SIFRA CRTEŽA 2/3	DATUM 18072-IDP-II-01.3-202-04	LISTOVA 1 LIST 1 BR. CRTEŽA IZMENA 04



- Legenda**
- Metoda A - Rucna sanacija
 - Farbanje ograde



R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR	REPUBLIKA SRBIJA - MGSJ / JP "ELEKTROPRIVREDA SRBIJE"		PROJEKAT
OBJEKAT	BRODSKA PREVODNICA HE "ĐERDAP 2"		IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVODNICE HE "ĐERDAP 2"
BROJ UGOVORA	DATUM	FAZA	CRTEŽ
18072-204	10.2019.	IDP	ĐERDAP 2 NIZVODNO PREDPRISTANIŠTE - REČNA STRANA SITUACIJA - PREGLED POVRŠINA KOJE TREBA TRETIRATI
ODG. PROJEKTANT	Vera Slović, dipl.inž.grad.	RJ	RAZMERA
UN. KONTROLA	Tamara Šumar, dipl.inž.grad.	110-202	LISTOVA
GL. PROJEKTANT	Todora Lazić, dipl.inž.el.	BEO PROJEKTA	LIST
		SIFRA CRTEŽA	1
		BR. CRTEŽAZIMENA	05
		2/3	18072-IDP-II-01.3-202-05




Legenda

- Metoda A - Rucna sanacija
- Farbanje ograde

Napomena: Kuke i bitve nisu u razmeri


R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR	REPUBLIKA SRBIJA - MGSJ / JP "ELEKTROPRIVREDA SRBIJE"		PROJEKAT
OBJEKAT	BRODSKA PREVODNICA HE "ĐERDAP 2"		IDEJNI PROJEKAT I STUDIJA OPRAVDANOSTI SANACIJA, ADAPTACIJA I REKONSTRUKCIJA BRODSKE PREVODNICE HE "ĐERDAP 2"
BROJ UGOVORA	DATUM	FAZA	CRTEŽ
18072-204	10.2019.	IDP	ĐERDAP 2 NIZVODNO PREDPRISTANIŠTE - OBALNA STRANA SITUACIJA - PREGLED POVRŠINA KOJE TREBA TRETIRATI
ODG. PROJEKTANT	Vera Slović, dipl.inž.grad.	RJ	RAZMERA
UN. KONTROLA	Tamara Šumar, dipl.inž.grad.	110-202	LISTOVA
GL. PROJEKTANT	Todora Lazić, dipl.inž.el.	BEO PROJEKTA	LIST
		SIFRA CRTEŽA	1
		BR. CRTEŽAZIMENA	
		2/3	06

OSNOVA
R 1:1000




X=4907500
Y=7625800

PRESEK A-A
R 1:500



Ivana Dmitrović

R.BR.	DATUM	OPIS IZMENE	POTPIS
ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR JP "ELEKTROPRIVREDA SRBIJE" OGRAK HE "ĐERDAP" - KLADOVO		PROJEKAT IDEJNI PROJEKAT ADAPTACIJE BRODSKE PREVODNICE HE "ĐERDAP 2"	
OBJEKAT BRODSKA PREVODNICA HE "ĐERDAP 2"		CRTEŽ SITUACIJA I POPREČNI PRESEK NASIPA U NIZVODNOM PREDPRISTANIŠTU - POSTOJEĆE STANJE -	
BROJ UGOVORA 18072-204	DATUM APRIL 2020.	FAZA IDP	
ODG. PROJEKT. Ivana Dmitrović, dipl.inž.gradj. br.licence: 314 F 401 07	RJ 110-201	RAZMERA 1:1000; 1:500; 1:100	LISTOVA 1
UN. KONTROLA Radmilo Glišić, dipl.inž.gradj.	DEO PROJEKTA HG	ŠIFRA CRTEŽA 18072-IDP-III-01-201-03	BR.CRT./IZMENA LIST 1
ŠEF PROJEKTA Todor Lazić, dipl.inž.el.			BR.CRT./IZMENA 03




KOORDINATE TAČKA
NOVOPROJEKTOVANOG OBJEKTA

TAČKA	X	Y
1	7625758.92	4907475.78
2	7625650.51	4907517.06
3	7625642.28	4907515.46
4	7625640.48	4907517.42
5	7625612.00	4907540.42
6	7625609.60	4907553.16
7	7625621.80	4907557.56
8	7625768.89	4907502.31
9	7625609.46	4907501.34
10	7625591.89	4907515.51
11	7625581.82	4907569.04
12	7625633.05	4907587.52
13	7625780.14	4907532.26
14	7625616.55	4907491.76
15	7625590.01	4907513.19
16	7625583.23	4907519.98
17	7625579.31	4907521.92
18	7625577.47	4907571.51
19	7625619.29	4907595.19
20	7625622.37	4907593.01
21	7625634.10	4907590.33
22	7625781.19	4907535.07

Ivana Dmitrović




PRESEK 1-1
R 1:500




DETALJ "A"

DETALJ "A"
R 1:100



PRESEK 2-2
R 1:500



R.BR.	DATUM	OPIS IZMENE	POTPIS
ME ENERGOPROJEKT-HIDROINŽENJERING A.D. BULEVAR MIHAILA PUPINA 12, BEOGRAD, SRBIJA			
INVESTITOR JP "ELEKTROPRIVREDA SRBIJE" OGRANAK HE "ĐERDAP" - KLADOVO		PROJEKAT IDEJNO REŠENJE ADAPTACIJE BRODSKE PREDVODNICE HE "ĐERDAP 2"	
OBJEKAT BRODSKA PREDVODNICA HE "ĐERDAP 2"		CRTEŽ SITUACIJA I POPREČNI PRESECI NASIPA U NIZVODNOM PREDPRISTANIŠTU - NOVOPROJEKTOVANO STANJE -	
BROJ UGOVORA 18072-204	DATUM APRIL 2020.	FAZA IDR	
ODG. PROJEKT. Ivana Dmitrović, dipl.inž.gradj. br.licence: 314 F 401 07	UN. KONTROLA Radmilo Glišić, dipl.inž.gradj.	RZ 110-201	RAZMERA 1:1000; 1:500; 1:100 LISTOVA 1
ŠEF PROJEKTA Todora Lazić, dipl.inž.el.	DEO PROJEKTA HG	ŠIFRA CRTEŽA 18072-IDR-III-03-201-04	BR.CRT./IZMENA 04